



RESERVE STUDIES | INSURANCE APPRAISALS | WIND MITIGATION

## Replacement Cost Valuation

The Moorings of Pinellas County Condominium

Tarpon Springs, Florida 34689

Prepared Exclusively for The Moorings of Pinellas County Condominium Association, Inc.

As of 1/3/2023 | FPAT File# REN2218820

**Felten Property Assessment Team**

866.568.7853 | [www.fpat.com](http://www.fpat.com)





January 03, 2023

The Moorings of Pinellas County Condominium Association, Inc.  
c/o Board of Directors  
450 Moorings Cove Dr  
Tarpon Springs, Florida 34689

Re: Replacement Cost Valuation - The Moorings of Pinellas County Condominium - FPAT  
File# REN2218820

Dear Board of Directors:

In accordance with your request and our agreement, Felten Professional Adjustment Team, LLC. has performed an Insurance Replacement Cost Valuation for The Moorings of Pinellas County Condominium located in Tarpon Springs, Florida. The purpose of this report is to establish accurate Hazard and Flood Insurance Replacement Costs for all buildings and site improvements insured by The Moorings of Pinellas County Condominium Association, Inc.. This report will ensure the Insurance Carrier is collecting accurate premiums and co-insurance requirement are properly met.

If you have any questions regarding this Replacement Cost Valuation Report, please contact us at (866)-568-7853. We look forward to doing business with you in the future.

Thank you,

Brad Felten, Managing Member  
Felten Property Assessment Team



# Introduction

This Replacement Cost Valuation has been prepared at the request of The Moorings of Pinellas County Condominium Association, Inc. for The Moorings of Pinellas County Condominium . The subject property is a Condominium Association located in Tarpon Springs, Florida. The purpose of this report is to establish accurate hazard and flood insurance replacement costs for all buildings and site improvements insured by The Moorings of Pinellas County Condominium Association, Inc.. This report will ensure the Insurance Carrier is collecting accurate premiums and co-insurance requirement are properly met.

This report is not a real-estate appraisal. The values displayed within this report represent only the replacement costs of the subject buildings and site improvements. It must be noted that estimated replacement cost values do not consider land value, market value or personal property. All elements of the buildings and site improvements that are considered relevant to the insurance policy have been thoroughly analyzed and inspected. The values presented in this report are subject to all assumptions, limiting conditions and certifications contained in this report.

A qualified representative of Felten Property Assessment Team (FPAT) performed a physical inspection of the property on January 03, 2023. The interior and exterior of all buildings and/or site improvements described in this Replacement Cost Valuation Report were inspected thoroughly to determine construction design, quality, size and occupancy. Building plans and association documents, where pertinent were reviewed.

## Subject of Report

This Replacement Cost Valuation Report contains the following risk(s):

### **Buildings :**

|                      |                          |                         |
|----------------------|--------------------------|-------------------------|
| Bldg 1, 8-Unit Risk  | 302-316 Moorings Cove Dr | <i>8-Unit, Type I</i>   |
| Bldg 2, 8-Unit Risk  | 318-332 Moorings Cove Dr | <i>8-Unit, Type II</i>  |
| Bldg 3, 8-Unit Risk  | 334-348 Moorings Cove Dr | <i>8-Unit, Type II</i>  |
| Bldg 4, 8-Unit Risk  | 350-364 Moorings Cove Dr | <i>8-Unit, Type III</i> |
| Bldg 5, 4-Unit Risk  | 366-372 Moorings Cove Dr | <i>4-Unit, Type I</i>   |
| Bldg 6, 8-Unit Risk  | 374-388 Moorings Cove Dr | <i>8-Unit, Type I</i>   |
| Bldg 7, 8-Unit Risk  | 404-432 Moorings Cove Dr | <i>8-Unit, Type IV</i>  |
| Bldg 9, 8-Unit Risk  | 373-387 Moorings Cove Dr | <i>8-Unit, Type IV</i>  |
| Bldg 10, 8-Unit Risk | 357-371 Moorings Cove Dr | <i>8-Unit, Type IV</i>  |
| Bldg 11, 8-Unit Risk | 341-355 Moorings Cove Dr | <i>8-Unit, Type IV</i>  |



|                      |                          |                 |
|----------------------|--------------------------|-----------------|
| Bldg 12, 8-Unit Risk | 325-339 Moorings Cove Dr | 8-Unit, Type IV |
| Clubhouse            | 450 Moorings Cove Dr     |                 |

**Property Site Improvements :**

|                      |
|----------------------|
| North Boat Dock      |
| South Boat Dock      |
| Bicycle Canopy       |
| Gazebo               |
| Perimeter Fence      |
| Pool Deck            |
| Pool Fence, Aluminum |
| Pool Fence, Vinyl    |
| Pool Heaters         |
| Swimming Pool        |



As a result of our replacement cost valuation investigation, we have estimated the total insurable replacement costs for all buildings and site improvements listed above and located at The Moorings of Pinellas County Condominium as of January 03, 2023 as follows:

### **Hazard Insurance**

|                            |                     |
|----------------------------|---------------------|
| Replacement Cost           | <b>\$13,377,625</b> |
| Less Insurance Exclusions  | <b>\$698,528</b>    |
| Insurable Replacement Cost | <b>\$12,679,097</b> |

### **Flood Insurance**

|                                 |                     |
|---------------------------------|---------------------|
| Replacement Cost                | <b>\$16,236,063</b> |
| NFIP Insurable Replacement Cost | <b>\$16,085,435</b> |



# Certification of Valuation

This is to certify the enclosed Replacement Cost Valuation report prepared at the request of The Moorings of Pinellas County Condominium Association, Inc. is the result of work performed by Felten Property Assessment Team and one or more of the individuals listed below.

In addition, we certify that, to the best of our knowledge and belief:

- All facts contained in this report are true and accurate.
- FPAT has no present or prospective interest in the subject property of this report, and also has no personal interest with respect to the parties involved.
- FPAT has no bias with respect to the subject property of this report or to the parties involved with this assignment.
- Our engagement in this assignment was not contingent upon producing or reporting predetermined results.
- Our compensation is not contingent on any action or event resulting from this report.
- We have the knowledge and experience to generate an accurate Replacement Cost Valuation for insurance purposes of all buildings and/or site improvements contained within this report.
- We have performed a physical inspection of the subject risk(s).

## **Key Staff:**

### **Brad Felten**

Sr. All-Lines Adjuster #E149535  
Flood Certification #06060373  
Certified Wind & Hurricane Mitigation Inspector  
Professional Reserve Analyst (PRA) # 2265

### **John Felten**

Sr. All-Lines Adjuster # D075772  
Flood Certification # 05030007  
Certified Building Contractor # CBC1255984  
Certified Wind & Hurricane Mitigation Inspector

### **Ian Wright**

All-Lines Adjuster # W273704  
Certified Wind & Hurricane Mitigation Inspector



Brad Felten, Managing Member





# Limiting Conditions

- The property description supplied to Felten Property Assessment Team, hereafter known as FPAT, is assumed to be correct.
- No survey of the property has been made or reviewed by FPAT, and no responsibility is assumed in connection with such matters. Illustrative material, including maps and plot plans, utilized in this report are included only to assist the reader in visualizing the property. Property dimensions and sizes are considered to be approximate.
- No responsibility is assumed for matters of a legal nature affecting title to the property, nor is any opinion of title rendered. Property titles are assumed to be good and merchantable unless otherwise stated.
- Information furnished by others is believed to be true, correct, and reliable. However, no responsibility for its accuracy is assumed by FPAT.
- All mortgages, liens, encumbrances, leases, and servitudes have been disregarded unless so specified within the report. The property is assumed to be under responsible, financially sound ownership and competent management.
- It is assumed that there are no hidden or unapparent conditions of the property, subsoil, or structures, which would render the property more or less valuable. No responsibility is assumed for such conditions or for arranging for engineering studies, which may be required to discover them.
- Unless otherwise stated in this report, the existence of hazardous material, which may or may not be present on the property, was not observed by FPAT. However, FPAT is not qualified to detect such substances. The presence of substances such as asbestos, urea-formaldehyde foam insulation, or other potentially hazardous materials may affect the value of the property. The value conclusions in this report are predicated on the assumption that there are no such materials on or in the property that would cause a loss of value. No responsibility is assumed for any such conditions, or for the expertise required to discover them. The client is urged to retain an expert in this field if desired. The analysis and value conclusions in this report are null and void should any hazardous material be discovered.
- Unless otherwise stated in this report, no environmental impact studies were either requested or made in conjunction with this report. FPAT reserves the rights to alter, amend, revise, or rescind any opinions of value based upon any subsequent environmental impact studies, research, or investigation.
- It is assumed that there is full compliance with all-applicable federal, state and local environmental regulations and laws unless noncompliance is specified, defined, and considered in this report.
- It is assumed that all applicable zoning and use regulations and restrictions have been complied with, unless non-conformity has been specified, defined and considered in this report.
- It is assumed that all required licenses, certificates of occupancy, consents, or other legislative or administrative authority from any local, state, or federal governmental or private entity or organization have been or can be obtained or renewed for any use on which the value estimate is based.



- FPAT will not be required to give testimony or appear in court because of having made this report, unless arrangements have previously been made.
- Possession of this report, or a copy thereof, does not carry with it the right of publication. It may not be used for any purpose by any person other than the client without the written consent of FPAT and in any event, only with properly written qualification and only in its entirety.
- Neither all nor any part of the contents of this report, or copy thereof, shall be conveyed to the public through advertising, public relations, news, sales, or any other media without written consent and approval of FPAT.
- The liability of FPAT, its employees, and subcontractors is limited to the client only.
- There is no accountability, obligation, or liability to any third party. If this report is placed in the hands of anyone other than the client, the client shall make such party aware of all limiting conditions and assumptions of the assignment and related discussions. FPAT is in no way responsible for any costs incurred to discover or correct any deficiencies of the property.
- The sole purpose of this report is for use in establishing insurance values.
- Acceptance and/or use of this report constitutes acceptance of the foregoing assumptions and limiting conditions.





# Valuation Update Service

This Replacement Cost Valuation Report can be updated annually or based on the requirements of the insurance carrier.

If there are any major changes to the subject risk(s) contained within this report or it has been five years since our last site analysis another inspection may be necessary. Normal maintenance does not require a physical inspection.

Please call us at 866-568-7853 or email us at [info@fpat.com](mailto:info@fpat.com) for pricing and more information.

*Note-Part of Chapter 718, Florida Statutes, addresses the independent insurance appraisal requirements for condominiums. Below is an excerpt from this Chapter which addresses this requirement.*

(Taken from Part I General Provisions, Chapter 718.104 Florida Statutes)

s. 718.104(4)(n) or the powers enumerated in subsection (3).

(11) INSURANCE.—In order to protect the safety, health, and welfare of the people of the State of Florida and to ensure consistency in the provision of insurance coverage to condominiums and their unit owners, this subsection applies to every residential condominium in the state, regardless of the date of its declaration of condominium. It is the intent of the Legislature to encourage lower or stable insurance premiums for associations described in this subsection.

(a) Adequate property insurance, regardless of any requirement in the declaration of condominium for coverage by the association for full insurable value, replacement cost, or similar coverage, must be based on the replacement cost of the property to be insured as determined by an independent insurance appraisal or update of a prior appraisal. The replacement cost must be determined at least once every 36 months.



# Reserve Study Information

Congratulations you have earned a significant discount on a Full Reserve Study for this property!

A Reserve Study is a long-term capital budget planning tool which identifies the current status of the reserve fund and a stable and equitable funding plan to offset ongoing deterioration, resulting in sufficient funds when those anticipated major common area expenditures actually occur. The reserve study consists of two parts: the physical analysis and the financial analysis.

Because of the extensive field work we have already completed in order to prepare this Replacement Cost Valuation, we are able to provide a significant discount on our Reserve Study Services.

To receive a **FREE** proposal simply click on the link below to fill out our easy to use web form.

[Click Here](#) to request Free Reserve Study Proposal

or Call **866-568-7853**

or Email [info@fpat.com](mailto:info@fpat.com)



# Methodology

To arrive at an accurate Replacement Cost Valuation estimate our team must first make a diligent effort to determine what the insurable items are and how they are insured. This is accomplished by consulting with property owners, property managers, insurance agents and reviewing pertinent documents. If the Replacement Cost Valuation is being performed for the first time or changes have taken place since the last inspection, a detailed site inspection will be conducted. One of our qualified team members will investigate building occupancy, size, building plans(when available), construction type, quality, finishes, etc. The subject risk(s) will be physically measured and a detailed sketch will be provided with the report. After all the property data is obtained the Replacement Cost Valuation and report process may begin. The estimated values in this report are arrived at through a number of methods, the primary method is the CoreLogic Commercial Express Building Valuation System. CoreLogic/MSB is the leading provider of building cost data, estimating software and property appraisal data to the insurance industry in the U.S. All relevant data is processed using a Reconstruction Cost Database. Reconstruction Cost provides the cost to reconstruct, at current prices, an exact duplicate or replica of the building, using like kind and quality materials, construction standards, design, layout and quality of workmanship. It is important to note the database used in this report recognizes the distinctions between Replacement Cost New and Reconstruction Cost with component-based or "total component" valuation and claims estimating technologies. Our total component estimating technologies calculate Reconstruction Cost by using formulas and databases to analyze and select detailed component parts of the buildings. Estimates are then assembled in a risk-specific manner, using local building codes, structural considerations and local material and labor costs. The distinctions between Replacement Cost New valuations and Reconstruction Cost valuations are important to understand because a carriers goal is to provide the insured with an equitable and fair settlement. Additionally, because policy and settlement terms are frequently subject to negotiation and court interpretation, it is essential that carriers receive premiums based on the fullest exposure on each building - the building's Reconstruction Cost.



# Explanations & Definitions

## Terminology

|                                     |   |
|-------------------------------------|---|
| <b>Additions</b>                    | Equipment, external structures, building items, site improvements, or miscellaneous adjustments added to the valuation. These items are added to the valuation in addition to the Gross Floor Area (e.g. balconies, exterior walkways, canopies, auxiliary generators). |
| <b>Architect's Fees</b>             | Architect's fees is compensation paid for architectural or engineering services rendered. The default percentage is 7% for commercial valuations and 0% for agricultural valuations.  |
| <b>Co-Insurance Requirement</b>     | The minimum amount of insurance that must be carried on the policy, usually 80%, but your co-insurance requirement for the policy may be different as determined by your company.   |
| <b>Depreciated Replacement Cost</b> | The remaining value after the deduction of Insurance Exclusions and Physical Depreciation from the Replacement Cost.  |
| <b>Depreciation</b>                 | The loss in value due to deterioration caused by usage, wear and tear, and the elements.  |
| <b>et al</b>                        | Meaning all other buildings insured by the client   |
| <b>Flood Insurance</b>              | Specific insurance coverage against property loss from flooding.  |
| <b>FPAT</b>                         | Felten Professional Adjustment Team, LLC.   |
| <b>Gross Floor Area (GFA)</b>       | The total floor area (measured in square feet) of all floors in the building considered in the Replacement Cost Valuation. Areas such as balconies, canopies, etc. are not included in the Gross Floor Area. These items are added to the valuation as "Additions".     |
| <b>Hazard Insurance</b>             | Insurance that protects a property owner against damage caused by fires, severe storms, earthquakes or other natural events. Hazard Insurance does not cover the peril of flooding.   |
| <b>HVAC</b>                         | Heating, Ventilation and Air-Conditioning Systems   |
| <b>Insurable Replacement Cost</b>   | The Replacement Cost of the building or site improvement less applicable Insurance Exclusions.  |
| <b>Insurable Responsibilities</b>   | Defines which parties are responsible for obtaining insurance coverage of the different building components.  |
| <b>Insurance Exclusions</b>         | Certain items of insured property are either not insured, or are specifically excluded from coverage, depending on the particular terms of an insurance policy. The three most common exclusions are: basement excavation; below grade foundations; underground         |



plumbing, piping, and conduits.

**Minimum Requirements**

Reporting requirements mandated by Citizens Property Insurance Corporation.

**New Construction**

The cost to replace at one time, an entire building of equal quality and utility. The prices used for labor, materials, overhead, profit, and fees are those in effect immediately prior to the occurrence of the loss. The replacement employs modern materials, current methods, designs, and layouts but does not take into consideration improvements necessary to conform to changed building codes, demolition, debris removal, site accessibility or site work, reuse of building components or services, extraordinary fees, premiums for materials or other contingencies. This is the methodology used for real estate appraisals. None of the calculations in this report are based on this methodology.

**NFIP**

National Flood Insurance Program managed by the Federal Emergency Management Agency (FEMA)

**Occupancy**

Building Occupancy refers to the categorizing structures based on their use.

**Overhead & Profit**

The general cost of operating and maintaining a business, in addition to specific costs related to a particular job, and the profit from construction activities is referred to as overhead and profit. The default percentage is 20% for commercial valuations and 16% for agricultural valuations .

**Partition Wall**

A load bearing or non-load bearing wall that defines an area.

**Party Wall**

A dividing wall between adjoining units that is shared by the tenants of each residence or business.

**Reconstruction**

The cost to construct, at current prices, an exact duplicate or replica of the building, using like kind and quality materials, construction standards, design, layout and quality of workmanship, built to current building regulations and codes. Reconstruction Cost also includes a number of site-specific and process-related costs that are experienced when rebuilding after a loss. Additional costs also include the added expense of reconstructing a structure with limited site mobility, access and owner involvement. All calculations in this report are based on this methodology.

**Replacement Cost**

In this report, the term Replacement Cost refers to the "Reconstruction Cost" as defined above.

**Type**

Used to distinguish between buildings with the same number of units of different construction and/or size. Usually for internal organizational purposes.

**Typical**

Buildings or site improvements that could be considered identical.



## Unit Abbreviations

|                       |                    |                                 |
|-----------------------|--------------------|---------------------------------|
| Sq Ft - Square Feet   | Lp Sm - Lump Sum   | Dbl Ct - Double Tennis Court    |
| Ln Ft - Linear Feet   | Allow - Allowance  | Ct - Court                      |
| Ea - Each             | Hp - Horsepower    | Units - Units                   |
| Sq Yds - Square Yards | Cu Ft - Cubic Feet | Cu Yds - Cubic Yards            |
| Kw - Kilowatts        | Pair - Pair        | Sq - Squares (1 Sq = 100 sq ft) |

## Structural Definitions

### **Commercial Construction Types:**

#### **Frame (Frame - ISO 1)**

A building where the exterior walls, bearing walls and partitions, and the structural floors and roof, and their supports, are wood or light-gauge metal. This includes buildings where the wood or light-gauge metal has been combined with other materials to form composite components such as wood or metal studs with brick or stone veneer, stucco, metal, vinyl, etc. siding. Buildings classified a ISO Class 1 are characteristic of this type.

#### **Masonry (Joisted Masonry - ISO 2)**

A building that has the exterior walls constructed of a material such as brick, hollow or solid concrete block, concrete, gypsum block, clay tile, stone, or similar materials. The structural floors and roof are of wood or light-gauge metal. Buildings classified as ISO Class 2 are characteristic of this type.

#### **Pre-Engineered Metal (Non-Combustible - ISO 3)**

A building that employs a system of pre-engineered rigid steel framing members. The exterior walls are of metal siding, sandwich panels, or masonry, and the roof is clad with metal roofing or sandwich panels. Buildings classified as ISO Class 3 are characteristic of this type.

#### **Steel Frame (Masonry Non-Combustible - ISO 4)**

A building where the structural floors and roof are of unprotected non-combustible materials such as metal decking or concrete on metal decking, and are supported by an unprotected structural steel frame, fire resistive exterior walls, or a combination of both. Buildings classified as ISO Class 4 are characteristic of this type.

#### **Protected Steel Frame (Modified Fire Resistive - ISO 5)**

A building where the structural floors and roof, and their supports are of non-combustible construction with a fire rating of not less than one hour. A building very similar to Construction





Type D Steel Frame; however, in Type E the non-combustible floor, roof, and framing components are protected with sprayed-fiber fireproofing. Buildings classified as ISO Class 5 are characteristic of this type.

### **Reinforced Concrete Frame (Fire Resistive - ISO 6)**

A building where the structural floors and roof, and their supports are of materials such as precast or poured-in-place reinforced concrete, with a fire resistive rating of not less than two hours. Buildings classified as ISO Class 6 are characteristic of this type.

## **Agricultural Construction Types:**

### **Frame**

A building where the exterior walls, bearing walls and partitions, and the structural floors and roof, and their supports, are wood or light-gauge metal. This includes buildings where the wood or light-gauge metal has been combined with other materials to form composite components such as wood or metal studs with brick or stone veneer, stucco, metal, vinyl, etc. siding.

### **Masonry**

A building that has the exterior walls constructed of a material such as brick, hollow or solid concrete block, concrete, gypsum block, clay tile, stone, or similar materials. The structural floors and roof are of wood or light-gauge metal.

### **Pre-Engineered Metal**

A building that employs a system of pre-engineered rigid steel framing members. The exterior walls are of metal siding, sandwich panels, or masonry, and the roof is clad with metal roofing or sandwich panels.

### **Pole Frame**

A building where the structural skeleton consists of timbers or poles. The poles or posts are set into the ground on top of concrete pads, and then back filled to anchor the post structure.

### **Structural Insulated Panel (SIP)**

A load bearing wall material, made up of rigid insulation sandwiched between two pieces of plywood or other material.



# Hazard Insurance Responsibilities

The hazard insurance replacement cost valuations contained in this report are based on Florida Statute 718 concerning condominiums. Under Florida Statute 718 the interior finishes of each condominium unit are the responsibility of the individual unit owners to insure. Any interior finishes located in common areas, owned by the association, have been included in the replacement cost valuations. Additionally, any buildings or site improvements not containing residential condominium units are the sole responsibility of the association to insure. The hazard insurance valuations do not include any personal property regardless of ownership.

Based Florida Statute 718 each individual unit owner is responsible for insuring the following components located within the individual unit:

- Any floor finishes such as carpet, tile, vinyl, etc.
- Any ceiling finishes such as paint, texture, suspended ceilings, etc.
- Any wall finishes such as paint, wallpaper, paneling, etc.
- Any electrical fixtures, plumbing fixtures, built-in cabinets, etc.

Florida Statute 718 has been amended several times since its origination. The amendment dated January 1, 2009 places the responsibility of insuring ALL heating & cooling (HVAC) equipment on the condominium association. The condominium association is responsible for insuring 100% of the building(s) HVAC equipment whether located on the roof, common area, ground, balcony or inside a residential unit. The duty to maintain, repair, or replace HVAC equipment servicing individually owned residential units is set by the declaration of condominium, while the duty to insure and repair after an "insurable event" or "casualty" is set by the statute.

The Hazard Insurance Valuations do not include foundations or plumbing below grade (insurance exclusions) or any personal property regardless of ownership.

The table on the following page is a Quick Reference Guide for determining insurable responsibilities.



## Hazard Insurance Quick Reference Table

AS GOVERNED BY FLORIDA STATUTE 718

| BUILDING COMPONENT   | ASSOCIATION RESPONSIBILITY | UNIT OWNER RESPONSIBILITY |
|--|----------------------------|---------------------------|
| 1. ROOF AND ROOF COVERING<br>Structural Framing and Roof Cover   | YES                        | NO                        |
| 2. EXTERIOR WALLS<br>Paint, Stucco, Insulation, Studs, Concrete Block, Brick, Doors, Windows, etc.   | YES                        | NO                        |
| 3. UNIT INTERIOR WALLS & CEILINGS<br>Party Walls & Ceilings, Unfinished drywall, Insulation, Metal, and Wood Studs   | YES                        | NO                        |
| 4a. COMMON AREA Interior Wall Studs, Block, and Drywall  | YES                        | NO                        |
| 4b. COMMON AREA Floor, Wall, and Ceiling Finishes  | YES                        | NO                        |
| 5. UNIT INTERIOR Floor, Wall, & Ceiling Finishes, Paint, Carpet, Tile, etc.  | NO                         | YES                       |
| 6. UNIT AND COMMON AREA <ul style="list-style-type: none"> <li>- Structural Floors</li> <li>- Structural Ceilings</li> <li>- Structural Walls</li> </ul>               | YES                        | NO                        |
| 7. COMMON AREA Air Conditioners  | YES                        | NO                        |
| 8. COMMON AREA Electrical  | YES                        | NO                        |
| 9. INTERIOR UNIT COMPONENTS <ul style="list-style-type: none"> <li>- Appliances</li> <li>- Electrical Fixtures</li> <li>- Water Heaters</li> <li>- Cabinets</li> </ul> | NO                         | YES                       |
| 10. INTERIOR UNIT Air Conditioners   | YES                        | NO                        |

\*\*\*The above information is intended to assist in determining the general responsibilities for both parties\*\*\*



# Flood Insurance Responsibilities

The Flood Insurance Replacement Cost Valuations contained in this report are based on the National Flood Insurance Program (NFIP).

**Loss Settlement:** According to the NFIP guidelines, buildings that do not meet one of the following requirements are not eligible for a RCV settlement:

1. A Single Family home insured to at least 80% of its Replacement Cost.
2. A Residential Condominium containing one or more family units insured to at least 80% of its Replacement Cost and in which at least 75% of the floor area is residential.

The NFIP utilizes three policy forms for structures based on their specific occupancy:

## Policy Forms

**Dwelling Form:** The Dwelling Policy Form may be issued to homeowners, residential renters, condominium unit-owners and owners of residential buildings containing two to four units. In communities participating in the National Flood Insurance Program (NFIP) Regular Program or Emergency Program the dwelling policy provides building and/or contents coverage for:

- Detached, single-family, non-condominium residence with incidental occupancy limited to less than 50% of the total floor area;
- Two- to four- family, non-condominium building with incidental occupancy limited to less than 25% of the total floor area;
- Dwelling unit in residential condominium building;
- Residential townhouse/rowhouse
- Manufactured mobile homes

**Dwelling Form Maximum Limits:** \$250,000

**General Form:** The General Property Policy Form may be issued to owners or lessees of non-residential buildings or units, or residential condominium buildings that are uninsurable under the Residential Condominium Building Association Policy (RCBAP). In communities participating in the NFIP Regular Program or Emergency Program the General Property Policy provides building and/or contents coverage for these and similar “other residential” risks:

- Hotel or motel with normal guest occupancy of 6 months or more;
- Apartment building;
- Residential cooperative building;
- Dormitory;
- Assisted-living facility.



And non-residential risks:

- Shop, restaurant, or other business;
- Mercantile building;
- Grain bin, silo, or other farm building;
- Agricultural or industrial processing facility;
- Factory;
- Warehouse;
- Poolhouse, clubhouse, or other recreational building;
- House of worship;
- School;
- Hotel or motel with normal guest occupancy of less than 6 months;
- Licensed bed-and-breakfast inn;
- Retail;
- Nursing home;
- Non-residential condominium;
- Condominium building with less than 75% of its total floor area in residential use;
- Detached garage;
- Tool shed;
- Stock, inventory, or other commercial contents.

**General Form Maximum Limits:** \$500,000

**RCBAP:** In order for a condominium building to be eligible under the Residential Condominium Building Association Policy (RCBAP) form, the building must be owned by a condominium association, which the NFIP defines as the entity made up of the unit owners responsible for the maintenance and operation of:

1. common elements owned in undivided shares by unit owners; and
2. other real property in which the unit owners have use rights

where membership in the entity is a required condition of unit ownership.

The RCBAP is required for all buildings owned by a condominium association containing 1 or more residential units and in which at least 75% of the total floor area within the building is residential without regard to the number of units or number of floors. The RCBAP is available for high-rise and lowrise residential condominium buildings, including townhouse/rowhouse and detached single-family condominium buildings in the Regular Program only.

Residential condominium buildings that are being used as a hotel or motel, or are being rented (either short or long term), must be insured under the RCBAP.



Only buildings having a condominium form of ownership are eligible for the RCBAP. If the named insured is listed as other than a condominium association, the agent/ producer must provide legal documentation to confirm that the insured is a condominium association before the RCBAP can be written. This documentation may be a copy of the condominium association by-laws or a statement signed by an officer or representative of the condominium association confirming that the building is in a condominium form of ownership. In the event of a loss, RCBAPs written for buildings found not to be in a condominium form of ownership will be rewritten under the correct policy form for up to the maximum amount of building coverage allowed under the program for the type of building insured, not to exceed the coverage purchased under the RCBAP.

A homeowners association (HOA) may differ from a condominium association and is ineligible for the RCBAP, unless the HOA meets the definition of a condominium association as defined in the policy. Cooperative ownership buildings are not eligible. Timeshare buildings in a condominium form of ownership in jurisdictions where title is vested in individual unit owners are eligible provided that all other criteria are met.

**RCBAP Form Maximum Limits:** Replacement cost, or the total number of units x \$250,000, whichever is less.

The Flood Insurance Valuations contained in this report do not include any personal property regardless of ownership. For more information regarding flood insurance visit [www.fema.gov](http://www.fema.gov)

The table on the following page is a Quick Reference Guide for determining insurable responsibilities.





## Flood Insurance Quick Reference Table

AS GOVERNED BY THE NATIONAL FLOOD INSURANCE PROGRAM-FEMA

| BUILDING COMPONENT   | ASSOCIATION RESPONSIBILITY | UNIT OWNER RESPONSIBILITY |
|--|----------------------------|---------------------------|
| 1. ROOF AND ROOF COVERING<br>Structural Framing and Roof Cover   | YES                        | NO                        |
| 2. EXTERIOR WALLS<br>Paint, Stucco, Insulation, Studs, Concrete Block, Brick, Doors, Windows, etc.   | YES                        | NO                        |
| 3. UNIT INTERIOR WALLS & CEILINGS<br>Party Walls & Ceilings, Unfinished drywall, Insulation, Metal, and Wood Studs   | YES                        | NO                        |
| 4a. COMMON AREA Interior Wall Studs, Block, and Drywall  | YES                        | NO                        |
| 4b. COMMON AREA Floor, Wall, and Ceiling Finishes  | YES                        | NO                        |
| 5. UNIT INTERIOR Floor, Wall, & Ceiling Finishes, Paint, Carpet, Tile, etc.  | YES                        | NO                        |
| 6. UNIT AND COMMON AREA <ul style="list-style-type: none"> <li>- Structural Floors</li> <li>- Structural Ceilings</li> <li>- Structural Walls</li> </ul>               | YES                        | NO                        |
| 7. COMMON AREA Air Conditioners  | YES                        | NO                        |
| 8. COMMON AREA Electrical  | YES                        | NO                        |
| 9. INTERIOR UNIT COMPONENTS <ul style="list-style-type: none"> <li>- Appliances</li> <li>- Electrical Fixtures</li> <li>- Water Heaters</li> <li>- Cabinets</li> </ul> | YES                        | NO                        |
| 10. INTERIOR UNIT Air Conditioners   | YES                        | NO                        |

\*\*\*The above information is intended to assist in determining the general responsibilities for both parties\*\*\*



# Recapitulation of Hazard Values

## The Moorings of Pinellas County Condominium

Tarpon Springs, Florida

HAZARD VALUATION as of January 03, 2023

FPAT File# REN2218820

| Building             | Replacement Cost    | Insurance Exclusions | Insurable Replacement Cost | Depreciation       | Depreciated Replacement Cost |
|----------------------|---------------------|----------------------|----------------------------|--------------------|------------------------------|
| Bldg 1, 8-Unit Risk  | \$950,514           | \$53,501             | \$897,013                  | \$466,447          | \$430,566                    |
| Bldg 2, 8-Unit Risk  | \$1,382,289         | \$73,395             | \$1,308,894                | \$680,625          | \$628,269                    |
| Bldg 3, 8-Unit Risk  | \$1,382,289         | \$73,395             | \$1,308,894                | \$680,625          | \$628,269                    |
| Bldg 4, 8-Unit Risk  | \$1,057,383         | \$58,415             | \$998,968                  | \$519,463          | \$479,505                    |
| Bldg 5, 4-Unit Risk  | \$527,640           | \$33,386             | \$494,254                  | \$242,184          | \$252,070                    |
| Bldg 6, 8-Unit Risk  | \$950,514           | \$53,501             | \$897,013                  | \$466,447          | \$430,566                    |
| Bldg 7, 8-Unit Risk  | \$1,220,599         | \$65,823             | \$1,154,776                | \$600,484          | \$554,292                    |
| Bldg 9, 8-Unit Risk  | \$1,220,599         | \$65,823             | \$1,154,776                | \$600,484          | \$554,292                    |
| Bldg 10, 8-Unit Risk | \$1,220,599         | \$65,823             | \$1,154,776                | \$600,484          | \$554,292                    |
| Bldg 11, 8-Unit Risk | \$1,220,599         | \$65,823             | \$1,154,776                | \$600,484          | \$554,292                    |
| Bldg 12, 8-Unit Risk | \$1,220,599         | \$65,823             | \$1,154,776                | \$600,484          | \$554,292                    |
| Clubhouse            | \$289,669           | \$23,820             | \$265,849                  | \$130,266          | \$135,583                    |
| <b>Total</b>         | <b>\$12,643,293</b> | <b>\$698,528</b>     | <b>\$11,944,765</b>        | <b>\$6,188,477</b> | <b>\$5,756,288</b>           |



| Property Site Improvement             | Replacement Cost |
|---------------------------------------|------------------|
| <b>Docks, Seawalls and Boardwalks</b> |                  |
| North Boat Dock                       | \$222,300        |
| South Boat Dock                       | \$250,500        |
| <b>Site Improvements</b>              |                  |
| Bicycle Canopy                        | \$1,068          |
| Gazebo                                | \$2,730          |
| <b>Swimming Pool Area</b>             |                  |
| Perimeter Fence                       | \$3,817          |
| Pool Deck                             | \$59,382         |
| Pool Fence, Aluminum                  | \$16,900         |
| Pool Fence, Vinyl                     | \$3,683          |
| Pool Heaters                          | \$11,000         |
| Swimming Pool                         | \$162,952        |
| <b>Total</b>                          | <b>\$734,332</b> |



# Recapitulation of Flood Values

## The Moorings of Pinellas County Condominium

Tarpon Springs, Florida

FLOOD VALUATION as of January 03, 2023

FPAT File# REN2218820

| Building             | Replacement Cost    | Insurance Exclusions | Depreciation       | Depreciated Replacement Cost | NFIP Insurable Replacement Cost |
|----------------------|---------------------|----------------------|--------------------|------------------------------|---------------------------------|
| Bldg 1, 8-Unit Risk  | \$1,250,016         | n/a                  | \$650,008          | \$600,008                    | \$1,250,016                     |
| Bldg 2, 8-Unit Risk  | \$1,845,483         | n/a                  | \$959,651          | \$885,832                    | \$1,845,483                     |
| Bldg 3, 8-Unit Risk  | \$1,845,483         | n/a                  | \$959,651          | \$885,832                    | \$1,845,483                     |
| Bldg 4, 8-Unit Risk  | \$1,397,107         | n/a                  | \$726,495          | \$670,612                    | \$1,397,107                     |
| Bldg 5, 4-Unit Risk  | \$679,694           | n/a                  | \$353,441          | \$326,253                    | \$679,694                       |
| Bldg 6, 8-Unit Risk  | \$1,250,016         | n/a                  | \$650,008          | \$600,008                    | \$1,250,016                     |
| Bldg 7, 8-Unit Risk  | \$1,535,719         | n/a                  | \$798,574          | \$737,145                    | \$1,535,719                     |
| Bldg 9, 8-Unit Risk  | \$1,535,719         | n/a                  | \$798,574          | \$737,145                    | \$1,535,719                     |
| Bldg 10, 8-Unit Risk | \$1,535,719         | n/a                  | \$798,574          | \$737,145                    | \$1,535,719                     |
| Bldg 11, 8-Unit Risk | \$1,535,719         | n/a                  | \$798,574          | \$737,145                    | \$1,535,719                     |
| Bldg 12, 8-Unit Risk | \$1,535,719         | n/a                  | \$798,574          | \$737,145                    | \$1,535,719                     |
| Clubhouse            | \$289,669           | n/a                  | \$150,628          | \$139,041                    | \$139,041                       |
| <b>Total</b>         | <b>\$16,236,063</b> |                      | <b>\$8,442,752</b> | <b>\$7,793,311</b>           | <b>\$16,085,435</b>             |

Excavation, below grade foundations, underground plumbing, piping, and conduits are not excluded from valuation for flood insurance coverage.



Felten Property Assessment Team | [www.fpat.com](http://www.fpat.com)  
FPAT File# REN2218820

# Aerial Property Photographs

**Aerial View of Property**









# Supplementary Valuation Information

## Commercial Residential Inspections/Valuations

### **Certification**

Name of the firm or key personnel completing the inspection/valuation:

Felten Property Assessment Team.

I, Brad Felten, certify that I, or the entity listed above, have/has at least three years experience in the field of commercial property inspections, commercial risk assessment, and commercial property replacement cost evaluation.

Date January 03, 2023 Position Managing Member

### **Property**

Property Owner's Name The Moorings of Pinellas County Condominium Association, Inc.

Property Address 450 Moorings Cove Dr

City Tarpon Springs

State, Zip Florida, 34689

### **Valuation Requirements**

- Inspections must include an estimate of the replacement cost for every structure to be covered.
- The method used to determine the cost of rebuilding the structures must be the current version of the calculation system. The system and version must be clearly indicated on the valuation documentation.
- Inspections must also include clear photographs of any building and ancillary structure the applicant/policyholder wishes to insure:
  - Main Structure
  - Pools
  - Docks, etc.
- If multiple buildings are identical, or nearly so, representative photographs may be used.
- Photographs of any existing damage must also be included.

### **Valuation Information**

- Year of construction 1976-1980
- Total number of units 84
- Number of owner-occupied units N/A
- Number of units rented on a long-term lease of 12 months or more N/A
- Number of units rented on a daily, weekly, or monthly basis N/A
- Number of units with time share occupancy N/A
- What is the distance to tidal water? Waterfront



## Building Descriptions

This section of the report contains a detailed building description for each different type of structure located on the property and insured by The Moorings of Pinellas County Condominium Association, Inc.. In many cases similar buildings may be described in the same description.

All building descriptions contained in this report meet or exceed Citizens Property Insurance Corporation Minimum Requirements for Non-licensed Commercial Residential Inspections/Valuation.



# Building Description

## Applicable Buildings

### 4-Unit Risk:

- 366-372 Moorings Cove Dr, Bldg 5

### 8-Unit Risk, Type I:

- 302-316 Moorings Cove Dr, Bldg 1
- 374-388 Moorings Cove Dr, Bldg 6

### 8-Unit Risk, Type II:

- 318-332 Moorings Cove Dr, Bldg 2
- 334-348 Moorings Cove Dr, Bldg 3

### 8-Unit Risk, Type III:

- 350-364 Moorings Cove Dr, Bldg 4

### 8-Unit Risk, Type IV:

- 404-432 Moorings Cove Dr, Bldg 7
- 373-387 Moorings Cove Dr, Bldg 9
- 357-371 Moorings Cove Dr, Bldg 10
- 341-355 Moorings Cove Dr, Bldg 11
- 323-339 Moorings Cove Dr, Bldg 12

## General Building Information

**Occupancy:** Condominium

**Square Footage:** **4-Unit Risk:**

- GFA: +/- 3,452 Sq Ft

### 8-Unit Risk, Type I:

- GFA: +/- 6,876 Sq Ft

### 8-Unit Risk, Type II:

- GFA: +/- 10,506 Sq Ft



**8-Unit Risk, Type III:**

- GFA: +/- 7,746 Sq Ft

**8-Unit Risk, Type IV:**

- GFA: +/- 9,142 Sq Ft

**Additions:**

**4-Unit Risk:**

- Ground Level Walkway +/- 102 Sq Ft
- Porch and Balconies +/- 102 Sq Ft
- Landing and Stairs +/- 95 Sq Ft
- Canopy +/- 134 Sq Ft

**8-Unit Risk, Type I:**

- Ground Level Walkway +/- 225 Sq Ft
- Porch and Balconies +/- 225 Sq Ft
- Landing and Stairs +/- 142 Sq Ft
- Canopy +/- 289 Sq Ft

**8-Unit Risk, Type II:**

- Ground Level Walkway +/- 200 Sq Ft
- Porch and Balconies +/- 200 Sq Ft
- Landing and Stairs +/- 154 Sq Ft
- Canopy +/- 264 Sq Ft

**8-Unit Risk, Type III:**

- Ground Level Walkway +/- 228 Sq Ft
- Porch and Balconies +/- 228 Sq Ft
- Landing and Stairs +/- 160 Sq Ft
- Canopy +/- 292 Sq Ft

**8-Unit Risk, Type IV:**

- Ground Level Walkway +/- 216 Sq Ft
- Porch and Balconies +/- 216 Sq Ft
- Landing and Stairs +/- 180 Sq Ft
- Canopy +/- 281 Sq Ft

**Condition:**

Good



**Year of Construction:** 1976

**# of Stories:** Two (2)

## Construction Analysis

**Foundation:** Estimated to be reinforced concrete footings

**Ground Subfloor:** Concrete slab on grade

**Elevated Subfloor(s):** Wood frame floor joists

**Exterior Walls:** Wood frame covered with vinyl siding

**Interior Partition Walls:** Wood studs

**Unit Party Walls:** Wood frame

**Roof Construction:** Wood truss decked with plywood

**Roof Shape:** Gable

**Roof Covering(s):** Composition shingles

**ISO Construction Type:** Frame (ISO 1)

## Mechanicals

**Elevators:** There are no elevators contained within these structures

**Heating & Cooling :** Split systems with condensing units located on the ground and air handlers located within individual units

**Electrical Wiring:** Copper - On the day of our inspection the electrical wiring was verified as copper at an electrical receptacle outlet inside a residential unit. **We did not verify the electrical wiring outside the residential units.**

**Fire Sprinklers:** No

**Manual Fire Alarm:** No

**Auto Dial-Out Fire Alarm:** No

## Finished Interior Common Areas

**Common Areas:** N/A - there are no finished interior common areas contained within these structures

**Common Floor Coverings:** N/A - there are no finished interior common areas contained within these structures



## BUILDING DESCRIPTION CONTINUED FROM PREVIOUS PAGE

|                               |   |
|-------------------------------|---|
| <b>Common Wall Finish:</b>    | N/A - there are no finished interior common areas contained within these structures |
| <b>Common Ceiling Finish:</b> | N/A - there are no finished interior common areas contained within these structures |
| <b>Common Kitchens:</b>       | N/A - there are no finished interior common areas contained within these structures |
| <b>Common Fireplaces:</b>     | N/A - there are no finished interior common areas contained within these structures |

### Interior Units

|                              |  |
|------------------------------|--|
| <b>Unit Floor Coverings:</b> | Each residential unit is individually owned with unit owner specific floor covering materials              |
| <b>Unit Wall Finish:</b>     | Painted textured drywall   |
| <b>Unit Ceiling Finish:</b>  | Painted textured drywall   |
| <b>Unit Kitchens:</b>        | Each unit contains one residential style kitchen with average quality cabinets, countertops and appliances |
| <b>Customized Features:</b>  | N/A - no major customized features verified at the time of inspection                                      |
| <b>Fireplaces:</b>           | None   |

### Supplementary Information

|                                       |      |
|---------------------------------------|------|
| <b>Business Exposure:</b>             | None |
| <b>Commercial Kitchens:</b>           | None |
| <b>Property or Liability Hazards:</b> | None |

**Additional Comments :**





# Building Description

## Applicable Buildings

### Clubhouse:

- 450 Moorings Cove Dr

## General Building Information

**Occupancy:** Clubhouse/Recreation

**Square Footage:** Clubhouse:

- GFA: +/- 1,343 Sq Ft

**Additions:** Clubhouse:

- Ground Level Walkway +/- 358 Sq Ft
- Canopy +/- 434

**Condition:** Good

**Year of Construction:** 1980

**# of Stories:** One (1)

## Construction Analysis

**Foundation:** Estimated to be reinforced concrete footings

**Ground Subfloor:** Concrete slab on grade

**Elevated Subfloor(s):** N/A - Does not apply to one story structures

**Exterior Walls:** Wood frame covered with vinyl siding

**Interior Partition Walls:** Wood studs

**Unit Party Walls:** N/A

**Roof Construction:** Wood truss decked with plywood

**Roof Shape:** Gable

**Roof Covering(s):** Composition shingles

**ISO Construction Type:** Frame (ISO 1)



## Mechanicals

|                                  |  |
|----------------------------------|--|
| <b>Elevators:</b>                | N/A - Does not apply to one story structures   |
| <b>Heating &amp; Cooling :</b>   | Split systems with condensing units located on the ground and air handlers located within the building.                                    |
| <b>Electrical Wiring:</b>        | Copper - On the day of our inspection the electrical wiring was verified as copper at an electrical receptacle outlet inside the building. |
| <b>Fire Sprinklers:</b>          | No   |
| <b>Manual Fire Alarm:</b>        | No   |
| <b>Auto Dial-Out Fire Alarm:</b> | No   |

## Finished Interior Common Areas

|                                |  |
|--------------------------------|--|
| <b>Common Areas:</b>           | Office, Clubhouse and Restrooms  |
| <b>Common Floor Coverings:</b> | Office: Laminate wood<br>Clubhouse: Laminate wood<br>Restrooms: Tile   |
| <b>Common Wall Finish:</b>     | Office: Painted textured drywall<br>Clubhouse: Painted textured drywall<br>Restrooms: Painted textured drywall |
| <b>Common Ceiling Finish:</b>  | Office: Painted textured drywall<br>Clubhouse: Painted textured drywall<br>Restrooms: Painted textured drywall |
| <b>Common Kitchens:</b>        | This building contains one (1) residential style kitchen with average quality appliances                       |
| <b>Common Fireplaces:</b>      | None   |

## Interior Units

|                              |  |
|------------------------------|--|
| <b>Unit Floor Coverings:</b> | N/A - there are no residential units contained within this structure |
| <b>Unit Wall Finish:</b>     | N/A - there are no residential units contained within this structure |
| <b>Unit Ceiling Finish:</b>  | N/A - there are no residential units contained within this structure |
| <b>Unit Kitchens:</b>        | N/A - there are no residential units contained within this structure |
| <b>Customized Features:</b>  | N/A - there are no residential units contained within this structure |
| <b>Fireplaces:</b>           | N/A - there are no residential units contained within this structure |



## Supplementary Information

**Business Exposure:** None

**Commercial Kitchens:** None

**Property or Liability Hazards:** None

**Additional Comments :**




## Building Sketches

This section of the report contains detailed floor by floor building sketches for each different type of structure located on the property and insured by The Moorings of Pinellas County Condominium Association, Inc.. In many cases identical buildings will be depicted with one sketch.


All building sketches contained in this report meet or exceed Citizens Property Insurance Corporation Minimum Requirements for Non-licensed Commercial Residential Inspections/Valuation.



# Building Sketch




**Level 1 of 2**


|   |  |  |                                 |
|---|--|--|---------------------------------|
| FELTEN PROPERTY ASSESSMENT TEAM                               |  |  | SKETCH DETAILS                  |
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  |  | The Moorings of Pinellas County |
| Phone: 866.568.7853   Email: info@fpat.com                    |  |  | Tarpon Springs, FL              |
| www.fpat.com  |  |  | 4-Unit Risk Building 5          |

Felten Property Assessment Team | 866.568.7853 | [info@fpat.com](mailto:info@fpat.com)


FPAT File# REN2218820

# Building Sketch




| FELTEN PROPERTY ASSESSMENT TEAM                               |  | SKETCH DETAILS                  |
|---|--|---------------------------------|
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  | The Moorings of Pinellas County |
| Phone: 866.568.7853   Email: info@fpat.com                    |  | Tarpon Springs, FL              |
| www.fpat.com  |  | 4-Unit Risk Building 5          |

# Building Sketch



**Level 1 of 2**


|   |  |  |  |
|---|--|--|--|
| FELTEN PROPERTY ASSESSMENT TEAM                               |  |  | SKETCH DETAILS                           |
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  |  | The Moorings of Pinellas County          |
| Phone: 866.568.7853   Email: info@fpat.com                    |  |  | Tarpon Springs, FL                       |
| www.fpat.com  |  |  | 8-Unit Risk, Type I<br>Buildings 1 and 6 |

Felten Property Assessment Team | 866.568.7853 | [info@fpat.com](mailto:info@fpat.com)

FPAT File# REN2218820



# Building Sketch




**Level 2 of 2**


| FELTEN PROPERTY ASSESSMENT TEAM                               |  | SKETCH DETAILS                           |
|---|--|--|
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  | The Moorings of Pinellas County          |
| Phone: 866.568.7853   Email: info@fpat.com                    |  | Tarpon Springs, FL                       |
| www.fpat.com  |  | 8-Unit Risk, Type I<br>Buildings 1 and 6 |



# Building Sketch




**Level 1 of 2**

|   |  |  |  |
|---|--|--|--|
| <b>FELTEN PROPERTY ASSESSMENT TEAM</b>                        |  |  | <b>SKETCH DETAILS</b>                  |
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  |  | The Moorings of Pinellas County        |
| Phone: 866.568.7853   Email: info@fpat.com                    |  |  | Tarpon Springs, FL                     |
| www.fpat.com  |  |  | 8-Unit Risk, Type II Buildings 2 and 3 |


Felten Property Assessment Team | 866.568.7853 | [info@fpat.com](mailto:info@fpat.com)

FPAT File# REN2218820

# Building Sketch




**Level 2 of 2**

| FELTEN PROPERTY ASSESSMENT TEAM                               |  |  | SKETCH DETAILS                         |
|---|--|--|--|
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  |  | The Moorings of Pinellas County        |
| Phone: 866.568.7853   Email: info@fpat.com                    |  |  | Tarpon Springs, FL                     |
| www.fpat.com  |  |  | 8-Unit Risk, Type II Buildings 2 and 3 |

Felten Property Assessment Team | 866.568.7853 | [info@fpat.com](mailto:info@fpat.com)

FPAT File# REN2218820

# Building Sketch




**Level 1 of 2**

| FELTEN PROPERTY ASSESSMENT TEAM                               |  | SKETCH DETAILS                   |
|---|--|----------------------------------|
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  | The Moorings of Pinellas County  |
| Phone: 866.568.7853   Email: info@fpat.com                    |  | Tarpon Springs, FL               |
| www.fpat.com  |  | 8-Unit Risk, Type III Building 4 |



# Building Sketch




**Level 2 of 2**


| FELTEN PROPERTY ASSESSMENT TEAM                               |  | SKETCH DETAILS                   |
|---|--|----------------------------------|
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  | The Moorings of Pinellas County  |
| Phone: 866.568.7853   Email: info@fpat.com                    |  | Tarpon Springs, FL               |
| www.fpat.com  |  | 8-Unit Risk, Type III Building 4 |



# Building Sketch




**Level 1 of 2**

| FELTEN PROPERTY ASSESSMENT TEAM                               |  |  | SKETCH DETAILS                               |
|---|--|--|--|
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  |  | The Moorings of Pinellas County              |
| Phone: 866.568.7853   Email: info@fpat.com                    |  |  | Tarpon Springs, FL                           |
| www.fpat.com  |  |  | 8-Unit Risk, Type IV<br>Buildings 7 and 9-12 |


Felten Property Assessment Team | 866.568.7853 | [info@fpat.com](mailto:info@fpat.com)

FPAT File# REN2218820

# Building Sketch



**Level 2 of 2**


| FELTEN PROPERTY ASSESSMENT TEAM                               |  |  | SKETCH DETAILS                               |
|---|--|--|--|
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  |  | The Moorings of Pinellas County              |
| Phone: 866.568.7853   Email: info@fpat.com                    |  |  | Tarpon Springs, FL                           |
| www.fpat.com  |  |  | 8-Unit Risk, Type IV<br>Buildings 7 and 9-12 |

Felten Property Assessment Team | 866.568.7853 | [info@fpat.com](mailto:info@fpat.com)

FPAT File# REN2218820



# Building Sketch



**Level 1 of 1**

| FELTEN PROPERTY ASSESSMENT TEAM                               |  | SKETCH DETAILS                  |
|---|--|---------------------------------|
| Insurance Appraisals - Reserve Studies - Windstorm Mitigation |  | The Moorings of Pinellas County |
| Phone: 866.568.7853   Email: info@fpat.com                    |  | Tarpon Springs, FL              |
| www.fpat.com  |  | Clubhouse                       |



## Photographs & Values

This section of the report contains detailed photographs and replacement cost values for each building and site improvement located on the property and insured by The Moorings of Pinellas County Condominium Association, Inc..



# Building Detail

Bldg 1, 8-Unit Risk  
302-316 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT<br>COST | NFIP INSURABLE<br>REPLACEMENT<br>COST |
|---------------------|---------------------------------------|
| \$1,250,016         | \$1,250,016                           |

## HAZARD INSURANCE

| REPLACEMENT<br>COST | INSURANCE<br>EXCLUSIONS | INSURABLE<br>REPLACEMENT<br>COST | DEPRECIATION | DEPRECIATED<br>REPLACEMENT<br>COST |
|---------------------|-------------------------|----------------------------------|--------------|------------------------------------|
| \$950,514           | \$53,501                | \$897,013                        | \$466,447    | \$430,566                          |

8-Unit, Type I



***Exterior Elevation Photographs***







***Roof Overview Photographs***



# Building Detail

Bldg 2, 8-Unit Risk  
318-332 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT<br>COST | NFIP INSURABLE<br>REPLACEMENT<br>COST |
|---------------------|---------------------------------------|
| \$1,845,483         | \$1,845,483                           |

## HAZARD INSURANCE

| REPLACEMENT<br>COST | INSURANCE<br>EXCLUSIONS | INSURABLE<br>REPLACEMENT<br>COST | DEPRECIATION | DEPRECIATED<br>REPLACEMENT<br>COST |
|---------------------|-------------------------|----------------------------------|--------------|------------------------------------|
| \$1,382,289         | \$73,395                | \$1,308,894                      | \$680,625    | \$628,269                          |

8-Unit, Type II





***Exterior Elevation Photographs***







***Roof Overview Photographs***



# Building Detail

Bldg 3, 8-Unit Risk  
334-348 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT COST | NFIP INSURABLE REPLACEMENT COST |
|------------------|---------------------------------|
| \$1,845,483      | \$1,845,483                     |

## HAZARD INSURANCE

| REPLACEMENT COST | INSURANCE EXCLUSIONS | INSURABLE REPLACEMENT COST | DEPRECIATION | DEPRECIATED REPLACEMENT COST |
|------------------|----------------------|----------------------------|--------------|------------------------------|
| \$1,382,289      | \$73,395             | \$1,308,894                | \$680,625    | \$628,269                    |

8-Unit, Type II





***Exterior Elevation Photographs***





***Roof Overview Photographs***





# Building Detail

Bldg 4, 8-Unit Risk  
350-364 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT<br>COST | NFIP INSURABLE<br>REPLACEMENT<br>COST |
|---------------------|---------------------------------------|
| \$1,397,107         | \$1,397,107                           |

## HAZARD INSURANCE

| REPLACEMENT<br>COST | INSURANCE<br>EXCLUSIONS | INSURABLE<br>REPLACEMENT<br>COST | DEPRECIATION | DEPRECIATED<br>REPLACEMENT<br>COST |
|---------------------|-------------------------|----------------------------------|--------------|------------------------------------|
| \$1,057,383         | \$58,415                | \$998,968                        | \$519,463    | \$479,505                          |

8-Unit, Type III



***Exterior Elevation Photographs***







***Roof Overview Photographs***



# Building Detail

Bldg 5, 4-Unit Risk  
366-372 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT<br>COST | NFIP INSURABLE<br>REPLACEMENT<br>COST |
|---------------------|---------------------------------------|
| \$679,694           | \$679,694                             |

## HAZARD INSURANCE

| REPLACEMENT<br>COST | INSURANCE<br>EXCLUSIONS | INSURABLE<br>REPLACEMENT<br>COST | DEPRECIATION | DEPRECIATED<br>REPLACEMENT<br>COST |
|---------------------|-------------------------|----------------------------------|--------------|------------------------------------|
| \$527,640           | \$33,386                | \$494,254                        | \$242,184    | \$252,070                          |

4-Unit, Type I





***Exterior Elevation Photographs***





***Roof Overview Photographs***





# Building Detail

Bldg 6, 8-Unit Risk  
374-388 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT COST | NFIP INSURABLE REPLACEMENT COST |
|------------------|---------------------------------|
| \$1,250,016      | \$1,250,016                     |

## HAZARD INSURANCE

| REPLACEMENT COST | INSURANCE EXCLUSIONS | INSURABLE REPLACEMENT COST | DEPRECIATION | DEPRECIATED REPLACEMENT COST |
|------------------|----------------------|----------------------------|--------------|------------------------------|
| \$950,514        | \$53,501             | \$897,013                  | \$466,447    | \$430,566                    |

8-Unit, Type I




***Exterior Elevation Photographs***







***Roof Overview Photographs***



# Building Detail

Bldg 7, 8-Unit Risk  
404-432 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT<br>COST | NFIP INSURABLE<br>REPLACEMENT<br>COST |
|---------------------|---------------------------------------|
| \$1,535,719         | \$1,535,719                           |

## HAZARD INSURANCE

| REPLACEMENT<br>COST | INSURANCE<br>EXCLUSIONS | INSURABLE<br>REPLACEMENT<br>COST | DEPRECIATION | DEPRECIATED<br>REPLACEMENT<br>COST |
|---------------------|-------------------------|----------------------------------|--------------|------------------------------------|
| \$1,220,599         | \$65,823                | \$1,154,776                      | \$600,484    | \$554,292                          |

8-Unit, Type IV





***Exterior Elevation Photographs***





***Roof Overview Photographs***





# Building Detail

Bldg 9, 8-Unit Risk  
373-387 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT COST | NFIP INSURABLE REPLACEMENT COST |
|------------------|---------------------------------|
| \$1,535,719      | \$1,535,719                     |

## HAZARD INSURANCE

| REPLACEMENT COST | INSURANCE EXCLUSIONS | INSURABLE REPLACEMENT COST | DEPRECIATION | DEPRECIATED REPLACEMENT COST |
|------------------|----------------------|----------------------------|--------------|------------------------------|
| \$1,220,599      | \$65,823             | \$1,154,776                | \$600,484    | \$554,292                    |

8-Unit, Type IV



***Exterior Elevation Photographs***







***Roof Overview Photographs***



# Building Detail

Bldg 10, 8-Unit Risk  
357-371 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT COST | NFIP INSURABLE REPLACEMENT COST |
|------------------|---------------------------------|
| \$1,535,719      | \$1,535,719                     |

## HAZARD INSURANCE

| REPLACEMENT COST | INSURANCE EXCLUSIONS | INSURABLE REPLACEMENT COST | DEPRECIATION | DEPRECIATED REPLACEMENT COST |
|------------------|----------------------|----------------------------|--------------|------------------------------|
| \$1,220,599      | \$65,823             | \$1,154,776                | \$600,484    | \$554,292                    |

8-Unit, Type IV



***Exterior Elevation Photographs***







***Roof Overview Photographs***



# Building Detail

Bldg 11, 8-Unit Risk  
341-355 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT COST | NFIP INSURABLE REPLACEMENT COST |
|------------------|---------------------------------|
| \$1,535,719      | \$1,535,719                     |

## HAZARD INSURANCE

| REPLACEMENT COST | INSURANCE EXCLUSIONS | INSURABLE REPLACEMENT COST | DEPRECIATION | DEPRECIATED REPLACEMENT COST |
|------------------|----------------------|----------------------------|--------------|------------------------------|
| \$1,220,599      | \$65,823             | \$1,154,776                | \$600,484    | \$554,292                    |

8-Unit, Type IV





***Exterior Elevation Photographs***



SUPPORTING PHOTOGRAPHS FOR: Bldg 11, 8-Unit Risk, 341-355 Moorings Cove Dr





***Roof Overview Photographs***





# Building Detail

Bldg 12, 8-Unit Risk  
325-339 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT<br>COST | NFIP INSURABLE<br>REPLACEMENT<br>COST |
|---------------------|---------------------------------------|
| \$1,535,719         | \$1,535,719                           |

## HAZARD INSURANCE

| REPLACEMENT<br>COST | INSURANCE<br>EXCLUSIONS | INSURABLE<br>REPLACEMENT<br>COST | DEPRECIATION | DEPRECIATED<br>REPLACEMENT<br>COST |
|---------------------|-------------------------|----------------------------------|--------------|------------------------------------|
| \$1,220,599         | \$65,823                | \$1,154,776                      | \$600,484    | \$554,292                          |

8-Unit, Type IV



***Exterior Elevation Photographs***







***Roof Overview Photographs***



# Building Detail

Clubhouse  
450 Moorings Cove Dr



## FLOOD INSURANCE

| REPLACEMENT<br>COST | NFIP INSURABLE<br>REPLACEMENT<br>COST |
|---------------------|---------------------------------------|
| \$289,669           | \$139,041                             |

According to the NFIP General Policy Form, flood insurance should be on an ACV basis with a maximum limit of \$500,000.

## HAZARD INSURANCE

| REPLACEMENT<br>COST | INSURANCE<br>EXCLUSIONS | INSURABLE<br>REPLACEMENT<br>COST | DEPRECIATION | DEPRECIATED<br>REPLACEMENT<br>COST |
|---------------------|-------------------------|----------------------------------|--------------|------------------------------------|
| \$289,669           | \$23,820                | \$265,849                        | \$130,266    | \$135,583                          |





***Exterior Elevation Photographs***



SUPPORTING PHOTOGRAPHS FOR: Clubhouse, 450 Moorings Cove Dr









***Roof Overview Photographs***









# Property Site Improvements Detail

| Property Improvement                  | Photo   | Description   | Replacement Cost |
|---------------------------------------|---|---|------------------|
| <b>Docks, Seawalls and Boardwalks</b> |   |   |                  |
| North Boat Dock                       |    | Wood frame boat dock with wood decking +/- 2,964 Sq Ft      | \$222,300        |
| South Boat Dock                       |    | Wood frame boat dock with composite decking +/- 3,340 Sq Ft | \$250,500        |
| <b>Site Improvements</b>              |   |   |                  |
| Bicycle Canopy                        |   | Wood frame bicycle canopy +/- 70 Sq Ft                      | \$1,068          |
| Gazebo                                |  | Wood frame gazebo   | \$2,730          |
| <b>Swimming Pool Area</b>             |   |   |                  |
| Perimeter Fence                       |  | 6' Vinyl shadow box privacy fencing +/- 57 Ln Ft            | \$3,817          |
| Pool Deck                             |  | Concrete pavers swimming pool deck +/- 3,612 Sq Ft          | \$59,382         |





SITE IMPROVEMENTS CONTINUED FROM PREVIOUS PAGE

| Property Improvement | Photo  | Description   | Replacement Cost |
|----------------------|--|---|------------------|
| Pool Fence, Aluminum |   | 6' Aluminum picket pool fencing +/- 130 Ln Ft   | \$16,900         |
| Pool Fence, Vinyl    |   | 6' Vinyl privacy pool fencing +/- 55 Ln Ft  | \$3,683          |
| Pool Heaters         |   | Pool heaters, electric heat pumps, 2 of 2   | \$11,000         |
| Swimming Pool        |  | Cast-in-place concrete or gunite sprayed-on concrete swimming pool +/- 865 Sq Ft, cost includes the pool, excavation, & filtering equipment | \$162,952        |



# Replacement Cost Calculations

This section of the report contains the CoreLogic Commercial Express calculations for each structure and/or site improvement located on the property and insured by The Moorings of Pinellas County Condominium Association, Inc.. In many cases identical buildings may be valued using the same replacement cost calculations.

All replacement cost calculations contained in this report meet or exceed Citizens Property Insurance Corporation Minimum Requirements for Non-licensed Commercial Residential Inspections/Valuation.





# Valuation Detailed Report

1/6/2023

## VALUATION

|                   |                |                  |            |
|-------------------|----------------|------------------|------------|
| Valuation Number: | REN2218820     | Effective Date:  | 01/06/2023 |
| Value Basis:      | Reconstruction | Expiration Date: | 01/06/2024 |
|                   |                | Cost as of:      | 06/2022    |

## BUSINESS

The Moorings of Pinellas County Condominium  
Moorings Cove Dr  
Tarpon Springs, FL 34689 USA

## LOCATION 1 - The Moorings of Pinellas County Condominium

The Moorings of Pinellas County Condominium  
Moorings Cove Dr  
Tarpon Springs, FL 34689 USA

### Location Adjustments

|                   |                     |
|-------------------|---------------------|
| Climatic Region:  | 3 - Warm            |
| High Wind Region: | 2 - Moderate Damage |
| Seismic Zone:     | 1 - No Damage       |

## BUILDING 1 - 4-Unit Risk, Bldg 5, Hazard

### Section1

#### SUPERSTRUCTURE

|                       |   |                       |        |
|-----------------------|---|-----------------------|--------|
| Occupancy:            | 100% Condominium, w/o Interior Finishes | Story Height:         | 10 ft. |
| Construction Type:    | 100% Frame (ISO 1)                      | Number of Stories:    | 2      |
| Gross Floor Area:     | 3,452 sq.ft.                            | Irregular Adjustment: | None   |
| Construction Quality: | 2.0 - Average                           |                       |        |
| Year Built:           |   |                       |        |

#### Adjustments

|               |                         |            |      |
|---------------|-------------------------|------------|------|
| Depreciation: | 49%                     | Condition: | Good |
|               | Effective Age: 41 years |            |      |

|                        |                        |                     |           |
|------------------------|------------------------|---------------------|-----------|
| Hillside Construction: | Degree of Slope: Level | Site Accessibility: | Excellent |
|                        | Site Position: Unknown | Soil Condition:     | Excellent |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

100 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

## Fees

Architect Fees: 7% is included  
Overhead and Profit: 20% is included

| SUMMARY OF COSTS      | User Provided                        | System Provided         | Reconstruction | Exclusion |
|-----------------------|--------------------------------------|-------------------------|----------------|-----------|
| <b>SUPERSTRUCTURE</b> |                                      |                         |                |           |
| Site Preparation      |                                      |                         |                | \$537     |
| Foundations           |                                      |                         | \$13,715       | \$22,349  |
| Foundation Wall       |                                      |                         |                |           |
| Interior Foundations  |                                      |                         |                |           |
| Slab On Ground        |                                      |                         |                |           |
| Exterior              |                                      |                         | \$153,679      |           |
| Framing               |                                      |                         |                |           |
| Exterior Wall         |                                      | 25% Wall Openings       |                |           |
| Exterior Wall         | 100% Siding, Metal or Other on Frame |                         |                |           |
| Structural Floor      |                                      |                         |                |           |
| Roof                  |                                      |                         | \$43,831       |           |
| Material              |                                      | 100% Shingles, Asphalt  |                |           |
| Pitch                 | 100% Low (2:12 to 6:12 pitch)        |                         |                |           |
| Interior              |                                      |                         | \$116,345      |           |
| Floor Finish          | 100% None                            |                         |                |           |
| Ceiling Finish        |                                      | 100% Drywall            |                |           |
| Partitions            |                                      |                         |                |           |
| Length                |                                      | 493 ft.                 |                |           |
| Structure             |                                      | 100% Studs, Girts, etc. |                |           |
| Finish                |                                      | 100% Drywall            |                |           |
| Mechanicals           |                                      |                         | \$117,148      | \$10,501  |
| Heating               | 93% Forced Warm Air                  |                         |                |           |
| Cooling               | 93% Forced Cool Air                  |                         |                |           |
| Fire Protection       |                                      |                         |                |           |
| Plumbing              |                                      | 24 Total Fixtures       |                |           |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

101 of 130





# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS                                       | User Provided | System Provided      | Reconstruction   | Exclusion       |
|--|---------------|----------------------|------------------|-----------------|
| Electrical   |               | 100% Average Quality |                  |                 |
| Elevators  |               |                      |                  |                 |
| Built-ins  |               |                      | \$41,182         |                 |
| SUBTOTAL RC  |               |                      | \$485,900        | \$33,386        |
| Depreciated Cost (51%)                                 |               |                      | \$247,809        | \$17,027        |
| ADDITIONS  |               |                      |                  |                 |
| Building Items   |               |                      | \$8,354          |                 |
| Total Additions  |               |                      | \$8,354          |                 |
| <b>TOTAL RC Section1</b>                               |               |                      | <b>\$494,254</b> | <b>\$33,386</b> |
| <b>TOTAL ACV</b>                                       |               |                      | <b>\$252,070</b> | <b>\$17,027</b> |
| <b>TOTAL RC BUILDING 1 4-Unit Risk, Bldg 5, Hazard</b> |               |                      | <b>\$494,254</b> | <b>\$33,386</b> |
| <b>TOTAL ACV</b>                                       |               |                      | <b>\$252,070</b> | <b>\$17,027</b> |

## BUILDING 2 - 4-Unit Risk, Bldg 5, Flood

### Section1

#### SUPERSTRUCTURE

|                       |                    |                       |        |
|-----------------------|--------------------|-----------------------|--------|
| Occupancy:            | 100% Condominium   | Story Height:         | 10 ft. |
| Construction Type:    | 100% Frame (ISO 1) | Number of Stories:    | 2      |
| Gross Floor Area:     | 3,452 sq.ft.       | Irregular Adjustment: | None   |
| Construction Quality: | 2.0 - Average      |                       |        |
| Year Built:           |                    |                       |        |

#### Adjustments

|                        |                         |                     |           |
|------------------------|-------------------------|---------------------|-----------|
| Depreciation:          | 52%                     | Condition:          | Good      |
|                        | Effective Age: 44 years |                     |           |
| Hillside Construction: | Degree of Slope: Level  | Site Accessibility: | Excellent |
|                        | Site Position: Unknown  | Soil Condition:     | Excellent |

#### Fees

|                      |                 |
|----------------------|-----------------|
| Architect Fees:      | 7% is included  |
| Overhead and Profit: | 20% is included |

| SUMMARY OF COSTS      | User Provided | System Provided | Reconstruction | Exclusion |
|-----------------------|---------------|-----------------|----------------|-----------|
| <b>SUPERSTRUCTURE</b> |               |                 |                |           |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

102 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS     | User Provided                                      | System Provided            | Reconstruction | Exclusion |
|----------------------|--|----------------------------|----------------|-----------|
| Site Preparation     |  |                            | \$523          |           |
| Foundations          |  |                            | \$35,131       |           |
| Foundation Wall      |  |                            |                |           |
| Interior Foundations |  |                            |                |           |
| Slab On Ground       |  |                            |                |           |
| Exterior             |  |                            | \$149,705      |           |
| Framing              |  |                            |                |           |
| Exterior Wall        |  | 25% Wall Openings          |                |           |
| Exterior Wall        | 100% Siding, Metal or Other on Frame               |                            |                |           |
| Structural Floor     |  |                            |                |           |
| Roof                 |  |                            | \$42,697       |           |
| Material             |  | 100% Shingles, Asphalt     |                |           |
| Pitch                | 100% Low (2:12 to 6:12 pitch)                      |                            |                |           |
| Interior             |  |                            | \$154,810      |           |
| Floor Finish         | 63% Carpet<br>20% Tile, Ceramic<br>10% Vinyl Sheet |                            |                |           |
| Ceiling Finish       |  | 100% Drywall<br>100% Paint |                |           |
| Partitions           |  |                            |                |           |
| Length               |  | 493 ft.                    |                |           |
| Structure            |  | 100% Studs, Girts, etc.    |                |           |
| Finish               |  | 100% Drywall<br>100% Paint |                |           |
| Mechanicals          |  |                            | \$242,050      |           |
| Heating              | 93% Forced Warm Air                                |                            |                |           |
| Cooling              | 93% Forced Cool Air                                |                            |                |           |
| Fire Protection      |  |                            |                |           |
| Plumbing             |  | 24 Total Fixtures          |                |           |
| Electrical           |  | 100% Average Quality       |                |           |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

103 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS         | User Provided | System Provided | Reconstruction   | Exclusion |
|--------------------------|---------------|-----------------|------------------|-----------|
| Elevators                |               |                 |                  |           |
| Built-ins                |               |                 | \$46,424         |           |
| SUBTOTAL RC              |               |                 | \$671,340        |           |
| Depreciated Cost (48%)   |               |                 | \$322,243        |           |
| ADDITIONS                |               |                 |                  |           |
| Building Items           |               |                 | \$8,354          |           |
| Total Additions          |               |                 | \$8,354          |           |
| <b>TOTAL RC Section1</b> |               |                 | <b>\$679,694</b> |           |
| <b>TOTAL ACV</b>         |               |                 | <b>\$326,253</b> |           |

|   |                  |
|---|------------------|
| <b>TOTAL RC BUILDING 2 4-Unit Risk, Bldg 5, Flood</b> | <b>\$679,694</b> |
| <b>TOTAL ACV</b>                                      | <b>\$326,253</b> |

## BUILDING 3 - 8-Unit Risk, Type I, Bldgs 1,6, Hazard

### Section1

#### SUPERSTRUCTURE

|                       |   |                       |        |
|-----------------------|---|-----------------------|--------|
| Occupancy:            | 100% Condominium, w/o Interior Finishes | Story Height:         | 10 ft. |
| Construction Type:    | 100% Frame (ISO 1)                      | Number of Stories:    | 2      |
| Gross Floor Area:     | 6,876 sq.ft.                            | Irregular Adjustment: | None   |
| Construction Quality: | 2.0 - Average                           |                       |        |
| Year Built:           |   |                       |        |

#### Adjustments

|               |                         |            |      |
|---------------|-------------------------|------------|------|
| Depreciation: | 52%                     | Condition: | Good |
|               | Effective Age: 44 years |            |      |

|                        |                        |                     |           |
|------------------------|------------------------|---------------------|-----------|
| Hillside Construction: | Degree of Slope: Level | Site Accessibility: | Excellent |
|                        | Site Position: Unknown | Soil Condition:     | Excellent |

#### Fees

|                      |                 |
|----------------------|-----------------|
| Architect Fees:      | 7% is included  |
| Overhead and Profit: | 20% is included |

| SUMMARY OF COSTS | User Provided | System Provided | Reconstruction | Exclusion |
|------------------|---------------|-----------------|----------------|-----------|
| SUPERSTRUCTURE   |               |                 |                |           |

|                  |  |  |         |  |
|------------------|--|--|---------|--|
| Site Preparation |  |  | \$1,069 |  |
|------------------|--|--|---------|--|

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

104 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS       | User Provided                        | System Provided         | Reconstruction | Exclusion |
|------------------------|--------------------------------------|-------------------------|----------------|-----------|
| Foundations            |                                      |                         | \$27,320       | \$32,305  |
| Foundation Wall        |                                      |                         |                |           |
| Interior Foundations   |                                      |                         |                |           |
| Slab On Ground         |                                      |                         |                |           |
| Exterior               |                                      |                         | \$242,121      |           |
| Framing                |                                      |                         |                |           |
| Exterior Wall          |                                      | 25% Wall Openings       |                |           |
| Exterior Wall          | 100% Siding, Metal or Other on Frame |                         |                |           |
| Structural Floor       |                                      |                         |                |           |
| Roof                   |                                      |                         | \$77,636       |           |
| Material               |                                      | 100% Shingles, Asphalt  |                |           |
| Pitch                  | 100% Low (2:12 to 6:12 pitch)        |                         |                |           |
| Interior               |                                      |                         | \$223,537      |           |
| Floor Finish           | 100% None                            |                         |                |           |
| Ceiling Finish         |                                      | 100% Drywall            |                |           |
| Partitions             |                                      |                         |                |           |
| Length                 |                                      | 982 ft.                 |                |           |
| Structure              |                                      | 100% Studs, Girts, etc. |                |           |
| Finish                 |                                      | 100% Drywall            |                |           |
| Mechanicals            |                                      |                         | \$227,554      | \$20,126  |
| Heating                | 93% Forced Warm Air                  |                         |                |           |
| Cooling                | 93% Forced Cool Air                  |                         |                |           |
| Fire Protection        |                                      |                         |                |           |
| Plumbing               |                                      | 46 Total Fixtures       |                |           |
| Electrical             |                                      | 100% Average Quality    |                |           |
| Elevators              |                                      |                         |                |           |
| Built-ins              |                                      |                         | \$82,029       |           |
| SUBTOTAL RC            |                                      |                         | \$880,198      | \$53,501  |
| Depreciated Cost (48%) |                                      |                         | \$422,495      | \$25,680  |
| ADDITIONS              |                                      |                         |                |           |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

105 of 130





# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

|   |                  |                 |
|---|------------------|-----------------|
| Building Items  | \$16,816         |                 |
| Total Additions   | \$16,816         |                 |
| <b>TOTAL RC Section1</b>  | <b>\$897,013</b> | <b>\$53,501</b> |
| <b>TOTAL ACV</b>  | <b>\$430,566</b> | <b>\$25,680</b> |
| <b>TOTAL RC BUILDING 3 8-Unit Risk, Type I, Bldgs 1,6, Hazard</b> | <b>\$897,013</b> | <b>\$53,501</b> |
| <b>TOTAL ACV</b>  | <b>\$430,566</b> | <b>\$25,680</b> |

## BUILDING 4 - 8-Unit Risk, Type I, Bldgs 1,6, Flood

### Section1

#### SUPERSTRUCTURE

|                       |                    |                       |        |
|-----------------------|--------------------|-----------------------|--------|
| Occupancy:            | 100% Condominium   | Story Height:         | 10 ft. |
| Construction Type:    | 100% Frame (ISO 1) | Number of Stories:    | 2      |
| Gross Floor Area:     | 6,876 sq.ft.       | Irregular Adjustment: | None   |
| Construction Quality: | 2.0 - Average      |                       |        |
| Year Built:           |                    |                       |        |

#### Adjustments

|                        |                         |                     |           |
|------------------------|-------------------------|---------------------|-----------|
| Depreciation:          | 52%                     | Condition:          | Good      |
|                        | Effective Age: 44 years |                     |           |
| Hillside Construction: | Degree of Slope: Level  | Site Accessibility: | Excellent |
|                        | Site Position: Unknown  | Soil Condition:     | Excellent |

#### Fees

|                      |                 |
|----------------------|-----------------|
| Architect Fees:      | 7% is included  |
| Overhead and Profit: | 20% is included |

| SUMMARY OF COSTS | User Provided | System Provided | Reconstruction | Exclusion |
|------------------|---------------|-----------------|----------------|-----------|
|------------------|---------------|-----------------|----------------|-----------|

#### SUPERSTRUCTURE

|                      |           |
|----------------------|-----------|
| Site Preparation     | \$1,042   |
| Foundations          | \$58,083  |
| Foundation Wall      |           |
| Interior Foundations |           |
| Slab On Ground       |           |
| Exterior             | \$235,860 |
| Framing              |           |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

106 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS       | User Provided                                      | System Provided            | Reconstruction | Exclusion |
|------------------------|--|----------------------------|----------------|-----------|
| Exterior Wall          |  | 25% Wall Openings          |                |           |
| Exterior Wall          | 100% Siding, Metal or Other on Frame               |                            |                |           |
| Structural Floor       |  |                            |                |           |
| Roof                   |  |                            | \$75,628       |           |
| Material               |  | 100% Shingles, Asphalt     |                |           |
| Pitch                  | 100% Low (2:12 to 6:12 pitch)                      |                            |                |           |
| Interior               |  |                            | \$299,230      |           |
| Floor Finish           | 63% Carpet<br>20% Tile, Ceramic<br>10% Vinyl Sheet |                            |                |           |
| Ceiling Finish         |  | 100% Drywall<br>100% Paint |                |           |
| Partitions             |  |                            |                |           |
| Length                 |  | 982 ft.                    |                |           |
| Structure              |  | 100% Studs, Girts, etc.    |                |           |
| Finish                 |  | 100% Drywall<br>100% Paint |                |           |
| Mechanicals            |  |                            | \$470,888      |           |
| Heating                | 93% Forced Warm Air                                |                            |                |           |
| Cooling                | 93% Forced Cool Air                                |                            |                |           |
| Fire Protection        |  |                            |                |           |
| Plumbing               |  | 46 Total Fixtures          |                |           |
| Electrical             |  | 100% Average Quality       |                |           |
| Elevators              |  |                            |                |           |
| Built-ins              |  |                            | \$92,471       |           |
| SUBTOTAL RC            |  |                            | \$1,233,201    |           |
| Depreciated Cost (48%) |  |                            | \$591,936      |           |
| ADDITIONS              |  |                            |                |           |
| Building Items         |  |                            | \$16,816       |           |
| Total Additions        |  |                            | \$16,816       |           |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

107 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

|                          |                    |
|--------------------------|--------------------|
| <b>TOTAL RC Section1</b> | <b>\$1,250,016</b> |
|--------------------------|--------------------|

|                  |                  |
|------------------|------------------|
| <b>TOTAL ACV</b> | <b>\$600,008</b> |
|------------------|------------------|

|  |                    |
|--|--------------------|
| <b>TOTAL RC BUILDING 4 8-Unit Risk, Type I, Bldgs 1,6, Flood</b> | <b>\$1,250,016</b> |
|--|--------------------|

|                  |                  |
|------------------|------------------|
| <b>TOTAL ACV</b> | <b>\$600,008</b> |
|------------------|------------------|

## BUILDING 5 - 8-Unit Risk, Type II, Bldgs 2,3, Hazard

### Section1

#### SUPERSTRUCTURE

|            |   |               |        |
|------------|---|---------------|--------|
| Occupancy: | 100% Condominium, w/o Interior Finishes | Story Height: | 10 ft. |
|------------|---|---------------|--------|

|                    |                    |                    |   |
|--------------------|--------------------|--------------------|---|
| Construction Type: | 100% Frame (ISO 1) | Number of Stories: | 2 |
|--------------------|--------------------|--------------------|---|

|                   |               |                       |      |
|-------------------|---------------|-----------------------|------|
| Gross Floor Area: | 10,506 sq.ft. | Irregular Adjustment: | None |
|-------------------|---------------|-----------------------|------|

|                       |               |
|-----------------------|---------------|
| Construction Quality: | 2.0 - Average |
|-----------------------|---------------|

Year Built:

#### Adjustments

|               |                         |            |      |
|---------------|-------------------------|------------|------|
| Depreciation: | 52%                     | Condition: | Good |
|               | Effective Age: 44 years |            |      |

|                        |                        |                     |           |
|------------------------|------------------------|---------------------|-----------|
| Hillside Construction: | Degree of Slope: Level | Site Accessibility: | Excellent |
|                        | Site Position: Unknown | Soil Condition:     | Excellent |

#### Fees

|                 |                |
|-----------------|----------------|
| Architect Fees: | 7% is included |
|-----------------|----------------|

|                      |                 |
|----------------------|-----------------|
| Overhead and Profit: | 20% is included |
|----------------------|-----------------|

| SUMMARY OF COSTS | User Provided | System Provided | Reconstruction | Exclusion |
|------------------|---------------|-----------------|----------------|-----------|
|------------------|---------------|-----------------|----------------|-----------|

#### SUPERSTRUCTURE

|                  |  |  |  |         |
|------------------|--|--|--|---------|
| Site Preparation |  |  |  | \$1,634 |
|------------------|--|--|--|---------|

|             |  |  |          |          |
|-------------|--|--|----------|----------|
| Foundations |  |  | \$41,742 | \$40,697 |
|-------------|--|--|----------|----------|

Foundation Wall

Interior Foundations

Slab On Ground

|          |  |  |           |  |
|----------|--|--|-----------|--|
| Exterior |  |  | \$324,545 |  |
|----------|--|--|-----------|--|

Framing

|               |                   |
|---------------|-------------------|
| Exterior Wall | 25% Wall Openings |
|---------------|-------------------|

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS   | User Provided                        | System Provided         | Reconstruction     | Exclusion       |
|--|--------------------------------------|-------------------------|--------------------|-----------------|
| Exterior Wall  | 100% Siding, Metal or Other on Frame |                         |                    |                 |
| Structural Floor   |                                      |                         |                    |                 |
| Roof   |                                      |                         | \$111,761          |                 |
| Material   |                                      | 100% Shingles, Asphalt  |                    |                 |
| Pitch  | 100% Low (2:12 to 6:12 pitch)        |                         |                    |                 |
| Interior   |                                      |                         | \$335,652          |                 |
| Floor Finish   | 100% None                            |                         |                    |                 |
| Ceiling Finish   |                                      | 100% Drywall            |                    |                 |
| Partitions   |                                      |                         |                    |                 |
| Length   |                                      | 1,500 ft.               |                    |                 |
| Structure  |                                      | 100% Studs, Girts, etc. |                    |                 |
| Finish   |                                      | 100% Drywall            |                    |                 |
| Mechanicals  |                                      |                         | \$354,166          | \$31,064        |
| Heating  | 98% Forced Warm Air                  |                         |                    |                 |
| Cooling  | 98% Forced Cool Air                  |                         |                    |                 |
| Fire Protection  |                                      |                         |                    |                 |
| Plumbing   |                                      | 71 Total Fixtures       |                    |                 |
| Electrical   |                                      | 100% Average Quality    |                    |                 |
| Elevators  |                                      |                         |                    |                 |
| Built-ins  |                                      |                         | \$125,335          |                 |
| SUBTOTAL RC  |                                      |                         | \$1,293,201        | \$73,395        |
| Depreciated Cost (48%)   |                                      |                         | \$620,736          | \$35,230        |
| ADDITIONS  |                                      |                         |                    |                 |
| Building Items   |                                      |                         | \$15,693           |                 |
| Total Additions  |                                      |                         | \$15,693           |                 |
| <b>TOTAL RC Section1</b>   |                                      |                         | <b>\$1,308,894</b> | <b>\$73,395</b> |
| <b>TOTAL ACV</b>   |                                      |                         | <b>\$628,269</b>   | <b>\$35,230</b> |
| <b>TOTAL RC BUILDING 5 8-Unit Risk, Type II, Bldgs 2,3, Hazard</b> |                                      |                         | <b>\$1,308,894</b> | <b>\$73,395</b> |
| <b>TOTAL ACV</b>   |                                      |                         | <b>\$628,269</b>   | <b>\$35,230</b> |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

109 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

## BUILDING 6 - 8-Unit Risk, Type II, Bldgs 2,3, Flood

### Section1

#### SUPERSTRUCTURE

|                       |                    |                       |        |
|-----------------------|--------------------|-----------------------|--------|
| Occupancy:            | 100% Condominium   | Story Height:         | 10 ft. |
| Construction Type:    | 100% Frame (ISO 1) | Number of Stories:    | 2      |
| Gross Floor Area:     | 10,506 sq.ft.      | Irregular Adjustment: | None   |
| Construction Quality: | 2.0 - Average      |                       |        |
| Year Built:           |                    |                       |        |

#### Adjustments

|                        |                         |                     |           |
|------------------------|-------------------------|---------------------|-----------|
| Depreciation:          | 52%                     | Condition:          | Good      |
|                        | Effective Age: 44 years |                     |           |
| Hillside Construction: | Degree of Slope: Level  | Site Accessibility: | Excellent |
|                        | Site Position: Unknown  | Soil Condition:     | Excellent |

#### Fees

|                      |                 |
|----------------------|-----------------|
| Architect Fees:      | 7% is included  |
| Overhead and Profit: | 20% is included |

| SUMMARY OF COSTS | User Provided | System Provided | Reconstruction | Exclusion |
|------------------|---------------|-----------------|----------------|-----------|
|------------------|---------------|-----------------|----------------|-----------|

#### SUPERSTRUCTURE

|                      |                                      |                        |           |  |
|----------------------|--------------------------------------|------------------------|-----------|--|
| Site Preparation     |                                      |                        | \$1,591   |  |
| Foundations          |                                      |                        | \$80,307  |  |
| Foundation Wall      |                                      |                        |           |  |
| Interior Foundations |                                      |                        |           |  |
| Slab On Ground       |                                      |                        |           |  |
| Exterior             |                                      |                        | \$316,151 |  |
| Framing              |                                      |                        |           |  |
| Exterior Wall        |                                      | 25% Wall Openings      |           |  |
| Exterior Wall        | 100% Siding, Metal or Other on Frame |                        |           |  |
| Structural Floor     |                                      |                        |           |  |
| Roof                 |                                      |                        | \$108,871 |  |
| Material             |                                      | 100% Shingles, Asphalt |           |  |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

110 of 130





# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS   | User Provided                                      | System Provided            | Reconstruction | Exclusion |
|--|--|----------------------------|----------------|-----------|
| Pitch  | 100% Low (2:12 to 6:12 pitch)                      |                            |                |           |
| Interior   |  |                            | \$453,566      |           |
| Floor Finish   | 68% Carpet<br>20% Tile, Ceramic<br>10% Vinyl Sheet |                            |                |           |
| Ceiling Finish   |  | 100% Drywall<br>100% Paint |                |           |
| Partitions   |  |                            |                |           |
| Length   |  | 1,500 ft.                  |                |           |
| Structure  |  | 100% Studs, Girts, etc.    |                |           |
| Finish   |  | 100% Drywall<br>100% Paint |                |           |
| Mechanicals  |  |                            | \$728,015      |           |
| Heating  | 98% Forced Warm Air                                |                            |                |           |
| Cooling  | 98% Forced Cool Air                                |                            |                |           |
| Fire Protection  |  |                            |                |           |
| Plumbing   |  | 71 Total Fixtures          |                |           |
| Electrical   |  | 100% Average Quality       |                |           |
| Elevators  |  |                            |                |           |
| Built-ins  |  |                            | \$141,288      |           |
| SUBTOTAL RC  |  |                            | \$1,829,790    |           |
| Depreciated Cost (48%)                                     |  |                            | \$878,299      |           |
| ADDITIONS  |  |                            |                |           |
| Building Items   |  |                            | \$15,693       |           |
| Total Additions  |  |                            | \$15,693       |           |
| TOTAL RC Section1  |  |                            | \$1,845,483    |           |
| TOTAL ACV  |  |                            | \$885,832      |           |
| TOTAL RC BUILDING 6 8-Unit Risk, Type II, Bldgs 2,3, Flood |  |                            | \$1,845,483    |           |
| TOTAL ACV  |  |                            | \$885,832      |           |
| BUILDING 7 - 8-Unit Risk, Type III, Bldg 4, Hazard         |  |                            |                |           |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

111 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

## Section1

### SUPERSTRUCTURE

|                       |   |                       |        |
|-----------------------|---|-----------------------|--------|
| Occupancy:            | 100% Condominium, w/o Interior Finishes | Story Height:         | 10 ft. |
| Construction Type:    | 100% Frame (ISO 1)                      | Number of Stories:    | 2      |
| Gross Floor Area:     | 7,746 sq.ft.                            | Irregular Adjustment: | None   |
| Construction Quality: | 2.0 - Average                           |                       |        |
| Year Built:           |   |                       |        |

### Adjustments

|                        |                         |                     |           |
|------------------------|-------------------------|---------------------|-----------|
| Depreciation:          | 52%                     | Condition:          | Good      |
|                        | Effective Age: 44 years |                     |           |
| Hillside Construction: | Degree of Slope: Level  | Site Accessibility: | Excellent |
|                        | Site Position: Unknown  | Soil Condition:     | Excellent |

### Fees

|                      |                 |
|----------------------|-----------------|
| Architect Fees:      | 7% is included  |
| Overhead and Profit: | 20% is included |

| SUMMARY OF COSTS | User Provided | System Provided | Reconstruction | Exclusion |
|------------------|---------------|-----------------|----------------|-----------|
|------------------|---------------|-----------------|----------------|-----------|

### SUPERSTRUCTURE

|                      |                                      |                        |           |          |
|----------------------|--------------------------------------|------------------------|-----------|----------|
| Site Preparation     |                                      |                        |           | \$1,204  |
| Foundations          |                                      |                        | \$30,776  | \$34,459 |
| Foundation Wall      |                                      |                        |           |          |
| Interior Foundations |                                      |                        |           |          |
| Slab On Ground       |                                      |                        |           |          |
| Exterior             |                                      |                        | \$262,622 |          |
| Framing              |                                      |                        |           |          |
| Exterior Wall        |                                      | 25% Wall Openings      |           |          |
| Exterior Wall        | 100% Siding, Metal or Other on Frame |                        |           |          |
| Structural Floor     |                                      |                        |           |          |
| Roof                 |                                      |                        | \$85,927  |          |
| Material             |                                      | 100% Shingles, Asphalt |           |          |
| Pitch                | 100% Low (2:12 to 6:12 pitch)        |                        |           |          |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

112 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS   | User Provided       | System Provided         | Reconstruction   | Exclusion       |
|--|---------------------|-------------------------|------------------|-----------------|
| Interior   |                     |                         | \$250,478        |                 |
| Floor Finish   | 100% None           |                         |                  |                 |
| Ceiling Finish   |                     | 100% Drywall            |                  |                 |
| Partitions   |                     |                         |                  |                 |
| Length   |                     | 1,106 ft.               |                  |                 |
| Structure  |                     | 100% Studs, Girts, etc. |                  |                 |
| Finish   |                     | 100% Drywall            |                  |                 |
| Mechanicals  |                     |                         | \$259,391        | \$22,751        |
| Heating  | 97% Forced Warm Air |                         |                  |                 |
| Cooling  | 97% Forced Cool Air |                         |                  |                 |
| Fire Protection  |                     |                         |                  |                 |
| Plumbing   |                     | 52 Total Fixtures       |                  |                 |
| Electrical   |                     | 100% Average Quality    |                  |                 |
| Elevators  |                     |                         |                  |                 |
| Built-ins  |                     |                         | \$92,408         |                 |
| SUBTOTAL RC  |                     |                         | \$981,603        | \$58,415        |
| Depreciated Cost (48%)   |                     |                         | \$471,169        | \$28,039        |
| ADDITIONS  |                     |                         |                  |                 |
| Building Items   |                     |                         | \$17,366         |                 |
| Total Additions  |                     |                         | \$17,366         |                 |
| <b>TOTAL RC Section1</b>   |                     |                         | <b>\$998,968</b> | <b>\$58,415</b> |
| <b>TOTAL ACV</b>   |                     |                         | <b>\$479,505</b> | <b>\$28,039</b> |
| <b>TOTAL RC BUILDING 7 8-Unit Risk, Type III, Bldg 4, Hazard</b> |                     |                         | <b>\$998,968</b> | <b>\$58,415</b> |
| <b>TOTAL ACV</b>   |                     |                         | <b>\$479,505</b> | <b>\$28,039</b> |

## BUILDING 8 - 8-Unit Risk, Type III, Bldg 4, Flood

### Section1

#### SUPERSTRUCTURE

|                    |                    |                    |        |
|--------------------|--------------------|--------------------|--------|
| Occupancy:         | 100% Condominium   | Story Height:      | 10 ft. |
| Construction Type: | 100% Frame (ISO 1) | Number of Stories: | 2      |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

113 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

Gross Floor Area: 7,746 sq.ft. Irregular Adjustment: None

Construction Quality: 2.0 - Average

Year Built:

## Adjustments

Depreciation: 52% Condition: Good  
Effective Age: 44 years

Hillside Construction: Degree of Slope: Level Site Accessibility: Excellent  
Site Position: Unknown Soil Condition: Excellent

## Fees

Architect Fees: 7% is included  
Overhead and Profit: 20% is included

| SUMMARY OF COSTS | User Provided | System Provided | Reconstruction | Exclusion |
|------------------|---------------|-----------------|----------------|-----------|
|------------------|---------------|-----------------|----------------|-----------|

## SUPERSTRUCTURE

|                      |  |                        |           |  |
|----------------------|--|------------------------|-----------|--|
| Site Preparation     |  |                        | \$1,173   |  |
| Foundations          |  |                        | \$63,548  |  |
| Foundation Wall      |  |                        |           |  |
| Interior Foundations |  |                        |           |  |
| Slab On Ground       |  |                        |           |  |
| Exterior             |  |                        | \$255,830 |  |
| Framing              |  |                        |           |  |
| Exterior Wall        |  | 25% Wall Openings      |           |  |
| Exterior Wall        | 100% Siding, Metal or Other on Frame               |                        |           |  |
| Structural Floor     |  |                        |           |  |
| Roof                 |  |                        | \$83,705  |  |
| Material             |  | 100% Shingles, Asphalt |           |  |
| Pitch                | 100% Low (2:12 to 6:12 pitch)                      |                        |           |  |
| Interior             |  |                        | \$337,322 |  |
| Floor Finish         | 67% Carpet<br>20% Tile, Ceramic<br>10% Vinyl Sheet |                        |           |  |
| Ceiling Finish       |  | 100% Drywall           |           |  |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

114 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS   | User Provided       | System Provided         | Reconstruction | Exclusion |
|--|---------------------|-------------------------|----------------|-----------|
|  |                     | 100% Paint              |                |           |
| Partitions   |                     |                         |                |           |
| Length   |                     | 1,106 ft.               |                |           |
| Structure  |                     | 100% Studs, Girts, etc. |                |           |
| Finish   |                     | 100% Drywall            |                |           |
|  |                     | 100% Paint              |                |           |
| Mechanicals  |                     |                         | \$533,992      |           |
| Heating  | 97% Forced Warm Air |                         |                |           |
| Cooling  | 97% Forced Cool Air |                         |                |           |
| Fire Protection  |                     |                         |                |           |
| Plumbing   |                     | 52 Total Fixtures       |                |           |
| Electrical   |                     | 100% Average Quality    |                |           |
| Elevators  |                     |                         |                |           |
| Built-ins  |                     |                         | \$104,171      |           |
| SUBTOTAL RC  |                     |                         | \$1,379,742    |           |
| Depreciated Cost (48%)                                   |                     |                         | \$662,276      |           |
| ADDITIONS  |                     |                         |                |           |
| Building Items   |                     |                         | \$17,366       |           |
| Total Additions  |                     |                         | \$17,366       |           |
| TOTAL RC Section1  |                     |                         | \$1,397,107    |           |
| TOTAL ACV  |                     |                         | \$670,612      |           |
| TOTAL RC BUILDING 8 8-Unit Risk, Type III, Bldg 4, Flood |                     |                         | \$1,397,107    |           |
| TOTAL ACV  |                     |                         | \$670,612      |           |

## BUILDING 9 - 8-Unit Risk, Type IV, Bldg 7,9-12, Hazard

### Section1

#### SUPERSTRUCTURE

|                    |   |                    |        |
|--------------------|---|--------------------|--------|
| Occupancy:         | 100% Condominium, w/o Interior Finishes | Story Height:      | 10 ft. |
| Construction Type: | 100% Frame (ISO 1)                      | Number of Stories: | 2      |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

115 of 130





# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

Gross Floor Area: 9,142 sq.ft. Irregular Adjustment: None

Construction Quality: 2.0 - Average

Year Built:

## Adjustments

Depreciation: 52% Condition: Good  
Effective Age: 44 years

Hillside Construction: Degree of Slope: Level Site Accessibility: Excellent  
Site Position: Unknown Soil Condition: Excellent

## Fees

Architect Fees: 7% is included  
Overhead and Profit: 20% is included

| SUMMARY OF COSTS | User Provided | System Provided | Reconstruction | Exclusion |
|------------------|---------------|-----------------|----------------|-----------|
|------------------|---------------|-----------------|----------------|-----------|

## SUPERSTRUCTURE

|                      |                                      |                        |           |          |
|----------------------|--------------------------------------|------------------------|-----------|----------|
| Site Preparation     |                                      |                        |           | \$1,422  |
| Foundations          |                                      |                        | \$36,323  | \$37,712 |
| Foundation Wall      |                                      |                        |           |          |
| Interior Foundations |                                      |                        |           |          |
| Slab On Ground       |                                      |                        |           |          |
| Exterior             |                                      |                        | \$294,458 |          |
| Framing              |                                      |                        |           |          |
| Exterior Wall        |                                      | 25% Wall Openings      |           |          |
| Exterior Wall        | 100% Siding, Metal or Other on Frame |                        |           |          |
| Structural Floor     |                                      |                        |           |          |
| Roof                 |                                      |                        | \$99,072  |          |
| Material             |                                      | 100% Shingles, Asphalt |           |          |
| Pitch                | 100% Low (2:12 to 6:12 pitch)        |                        |           |          |
| Interior             |                                      |                        | \$293,747 |          |
| Floor Finish         | 100% None                            |                        |           |          |
| Ceiling Finish       |                                      | 100% Drywall           |           |          |
| Partitions           |                                      |                        |           |          |
| Length               |                                      | 1,306 ft.              |           |          |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

116 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS   | User Provided       | System Provided         | Reconstruction     | Exclusion       |
|--|---------------------|-------------------------|--------------------|-----------------|
| Structure  |                     | 100% Studs, Girts, etc. |                    |                 |
| Finish   |                     | 100% Drywall            |                    |                 |
| Mechanicals  |                     |                         | \$304,947          | \$26,689        |
| Heating  | 97% Forced Warm Air |                         |                    |                 |
| Cooling  | 97% Forced Cool Air |                         |                    |                 |
| Fire Protection  |                     |                         |                    |                 |
| Plumbing   |                     | 61 Total Fixtures       |                    |                 |
| Electrical   |                     | 100% Average Quality    |                    |                 |
| Elevators  |                     |                         |                    |                 |
| Built-ins  |                     |                         | \$109,062          |                 |
| SUBTOTAL RC  |                     |                         | \$1,137,608        | \$65,823        |
| Depreciated Cost (48%)   |                     |                         | \$546,052          | \$31,595        |
| ADDITIONS  |                     |                         |                    |                 |
| Building Items   |                     |                         | \$17,168           |                 |
| Total Additions  |                     |                         | \$17,168           |                 |
| <b>TOTAL RC Section1</b>   |                     |                         | <b>\$1,154,776</b> | <b>\$65,823</b> |
| <b>TOTAL ACV</b>   |                     |                         | <b>\$554,292</b>   | <b>\$31,595</b> |
| <b>TOTAL RC BUILDING 9 8-Unit Risk, Type IV, Bldg 7,9-12, Hazard</b> |                     |                         |                    |                 |
|  |                     |                         | <b>\$1,154,776</b> | <b>\$65,823</b> |
| <b>TOTAL ACV</b>   |                     |                         |                    |                 |
|  |                     |                         | <b>\$554,292</b>   | <b>\$31,595</b> |

## BUILDING 10 - 8-Unit Risk, Type IV, Bldg 7,9-12, Flood

### Section1

#### SUPERSTRUCTURE

|                    |                    |                       |        |
|--------------------|--------------------|-----------------------|--------|
| Occupancy:         | 100% Condominium   | Story Height:         | 10 ft. |
| Construction Type: | 100% Frame (ISO 1) | Number of Stories:    | 2      |
| Gross Floor Area:  | 9,142 sq.ft.       | Irregular Adjustment: | None   |

Construction Quality: 2.0 - Average

Year Built:

#### Adjustments

|                         |     |            |      |
|-------------------------|-----|------------|------|
| Depreciation:           | 52% | Condition: | Good |
| Effective Age: 44 years |     |            |      |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

|                        |                        |                     |           |
|------------------------|------------------------|---------------------|-----------|
| Hillside Construction: | Degree of Slope: Level | Site Accessibility: | Excellent |
|                        | Site Position: Unknown | Soil Condition:     | Excellent |

## Fees

|                      |                 |
|----------------------|-----------------|
| Architect Fees:      | 7% is included  |
| Overhead and Profit: | 20% is included |

| SUMMARY OF COSTS | User Provided | System Provided | Reconstruction | Exclusion |
|------------------|---------------|-----------------|----------------|-----------|
|------------------|---------------|-----------------|----------------|-----------|

## SUPERSTRUCTURE

|                      |                                      |                         |           |  |
|----------------------|--------------------------------------|-------------------------|-----------|--|
| Site Preparation     |                                      |                         | \$1,385   |  |
| Foundations          |                                      |                         | \$72,121  |  |
| Foundation Wall      |                                      |                         |           |  |
| Interior Foundations |                                      |                         |           |  |
| Slab On Ground       |                                      |                         |           |  |
| Exterior             |                                      |                         | \$286,842 |  |
| Framing              |                                      |                         |           |  |
| Exterior Wall        |                                      | 25% Wall Openings       |           |  |
| Exterior Wall        | 100% Siding, Metal or Other on Frame |                         |           |  |
| Structural Floor     |                                      |                         |           |  |
| Roof                 |                                      |                         | \$96,510  |  |
| Material             |                                      | 100% Shingles, Asphalt  |           |  |
| Pitch                | 100% Low (2:12 to 6:12 pitch)        |                         |           |  |
| Interior             |                                      |                         | \$310,835 |  |
| Floor Finish         | 100% None                            |                         |           |  |
| Ceiling Finish       |                                      | 100% Drywall            |           |  |
|                      |                                      | 100% Paint              |           |  |
| Partitions           |                                      |                         |           |  |
| Length               |                                      | 1,306 ft.               |           |  |
| Structure            |                                      | 100% Studs, Girts, etc. |           |  |
| Finish               |                                      | 100% Drywall            |           |  |
|                      |                                      | 100% Paint              |           |  |
| Mechanicals          |                                      |                         | \$627,914 |  |
| Heating              | 97% Forced Warm Air                  |                         |           |  |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

118 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS   | User Provided       | System Provided      | Reconstruction     | Exclusion |
|--|---------------------|----------------------|--------------------|-----------|
| Cooling  | 97% Forced Cool Air |                      |                    |           |
| Fire Protection  |                     |                      |                    |           |
| Plumbing   |                     | 61 Total Fixtures    |                    |           |
| Electrical   |                     | 100% Average Quality |                    |           |
| Elevators  |                     |                      |                    |           |
| Built-ins  |                     |                      | \$122,945          |           |
| SUBTOTAL RC  |                     |                      | \$1,518,551        |           |
| Depreciated Cost (48%)   |                     |                      | \$728,905          |           |
| ADDITIONS  |                     |                      |                    |           |
| Building Items   |                     |                      | \$17,168           |           |
| Total Additions  |                     |                      | \$17,168           |           |
| <b>TOTAL RC Section1</b>   |                     |                      | <b>\$1,535,719</b> |           |
| <b>TOTAL ACV</b>   |                     |                      | <b>\$737,145</b>   |           |
| <b>TOTAL RC BUILDING 10 8-Unit Risk, Type IV, Bldg 7,9-12, Flood</b> |                     |                      | <b>\$1,535,719</b> |           |
| <b>TOTAL ACV</b>   |                     |                      | <b>\$737,145</b>   |           |

## BUILDING 11 - Clubhouse, Hazard

### Section1

#### SUPERSTRUCTURE

|                        |                                    |                       |           |
|------------------------|------------------------------------|-----------------------|-----------|
| Occupancy:             | 100% Clubhouse/Recreation Building | Story Height:         | 11 ft.    |
| Construction Type:     | 100% Frame (ISO 1)                 | Number of Stories:    | 1         |
| Gross Floor Area:      | 1,343 sq.ft.                       | Irregular Adjustment: | None      |
| Construction Quality:  | 2.0 - Average                      |                       |           |
| Year Built:            |                                    |                       |           |
| <b>Adjustments</b>     |                                    |                       |           |
| Depreciation:          | 49%                                | Condition:            | Good      |
|                        | Effective Age: 41 years            |                       |           |
| Hillside Construction: | Degree of Slope: Level             | Site Accessibility:   | Excellent |
|                        | Site Position: Unknown             | Soil Condition:       | Excellent |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

119 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

## Fees

Architect Fees: 7% is included  
Overhead and Profit: 20% is included

| SUMMARY OF COSTS      | User Provided                                     | System Provided            | Reconstruction | Exclusion |
|-----------------------|---|----------------------------|----------------|-----------|
| <b>SUPERSTRUCTURE</b> |   |                            |                |           |
| Site Preparation      |   |                            |                | \$400     |
| Foundations           |   |                            | \$10,212       | \$13,261  |
| Foundation Wall       |   |                            |                |           |
| Interior Foundations  |   |                            |                |           |
| Slab On Ground        |   |                            |                |           |
| Exterior              |   |                            | \$60,543       |           |
| Framing               |   |                            |                |           |
| Exterior Wall         |   | 35% Wall Openings          |                |           |
| Exterior Wall         | 100% Siding, Metal or<br>Other on Frame           |                            |                |           |
| Structural Floor      |   |                            |                |           |
| Roof                  |   |                            | \$32,163       |           |
| Material              |   | 100% Shingles,<br>Asphalt  |                |           |
| Pitch                 | 100% Low (2:12 to<br>6:12 pitch)                  |                            |                |           |
| Interior              |   |                            | \$30,669       |           |
| Floor Finish          | 18% Tile, Ceramic<br>62% Tile, Vinyl<br>Composite |                            |                |           |
| Ceiling Finish        | 100% Drywall<br>100% Paint                        |                            |                |           |
| Partitions            |   |                            |                |           |
| Length                |   | 44 ft.                     |                |           |
| Structure             |   | 100% Studs, Girts,<br>etc. |                |           |
| Finish                | 100% Drywall<br>100% Paint                        |                            |                |           |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

120 of 130





# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS                              | User Provided        | System Provided      | Reconstruction   | Exclusion       |
|---|----------------------|----------------------|------------------|-----------------|
| Mechanicals                                   |                      |                      | \$114,353        | \$10,158        |
| Heating                                       | 100% Forced Warm Air |                      |                  |                 |
| Cooling                                       | 100% Forced Cool Air |                      |                  |                 |
| Fire Protection                               |                      |                      |                  |                 |
| Plumbing                                      | 9 Total Fixtures     |                      |                  |                 |
| Electrical                                    |                      | 100% Average Quality |                  |                 |
| Elevators                                     |                      |                      |                  |                 |
| Built-ins                                     |                      |                      | \$4,595          |                 |
| SUBTOTAL RC                                   |                      |                      | \$252,535        | \$23,820        |
| Depreciated Cost (51%)                        |                      |                      | \$128,793        | \$12,148        |
| ADDITIONS                                     |                      |                      |                  |                 |
| Building Items                                |                      |                      | \$13,314         |                 |
| Total Additions                               |                      |                      | \$13,314         |                 |
| <b>TOTAL RC Section1</b>                      |                      |                      | <b>\$265,849</b> | <b>\$23,820</b> |
| <b>TOTAL ACV</b>                              |                      |                      | <b>\$135,583</b> | <b>\$12,148</b> |
| <b>TOTAL RC BUILDING 11 Clubhouse, Hazard</b> |                      |                      | <b>\$265,849</b> | <b>\$23,820</b> |
| <b>TOTAL ACV</b>                              |                      |                      | <b>\$135,583</b> | <b>\$12,148</b> |

## BUILDING 12 - Clubhouse, Flood

### Section1

#### SUPERSTRUCTURE

|                       |                                    |                       |        |
|-----------------------|------------------------------------|-----------------------|--------|
| Occupancy:            | 100% Clubhouse/Recreation Building | Story Height:         | 11 ft. |
| Construction Type:    | 100% Frame (ISO 1)                 | Number of Stories:    | 1      |
| Gross Floor Area:     | 1,343 sq.ft.                       | Irregular Adjustment: | None   |
| Construction Quality: | 2.0 - Average                      |                       |        |
| Year Built:           |                                    |                       |        |

#### Adjustments

|               |                         |            |      |
|---------------|-------------------------|------------|------|
| Depreciation: | 52%                     | Condition: | Good |
|               | Effective Age: 44 years |            |      |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

121 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

---

|                        |                        |                     |           |
|------------------------|------------------------|---------------------|-----------|
| Hillside Construction: | Degree of Slope: Level | Site Accessibility: | Excellent |
|                        | Site Position: Unknown | Soil Condition:     | Excellent |

## Fees

|                      |                 |
|----------------------|-----------------|
| Architect Fees:      | 7% is included  |
| Overhead and Profit: | 20% is included |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

122 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS      | User Provided                           | System Provided            | Reconstruction | Exclusion |
|-----------------------|---|----------------------------|----------------|-----------|
| <b>SUPERSTRUCTURE</b> |   |                            |                |           |
| Site Preparation      |   |                            | \$400          |           |
| Foundations           |   |                            | \$23,473       |           |
| Foundation Wall       |   |                            |                |           |
| Interior Foundations  |   |                            |                |           |
| Slab On Ground        |   |                            |                |           |
| Exterior              |   |                            | \$60,543       |           |
| Framing               |   |                            |                |           |
| Exterior Wall         |   | 35% Wall Openings          |                |           |
| Exterior Wall         | 100% Siding, Metal or<br>Other on Frame |                            |                |           |
| Structural Floor      |   |                            |                |           |
| Roof                  |   |                            | \$32,163       |           |
| Material              |   | 100% Shingles,<br>Asphalt  |                |           |
| Pitch                 | 100% Low (2:12 to<br>6:12 pitch)        |                            |                |           |
| Interior              |   |                            | \$30,669       |           |
| Floor Finish          | 18% Tile, Ceramic                       |                            |                |           |
|                       | 62% Tile, Vinyl<br>Composite            |                            |                |           |
| Ceiling Finish        | 100% Drywall                            |                            |                |           |
|                       | 100% Paint                              |                            |                |           |
| Partitions            |   |                            |                |           |
| Length                |   | 44 ft.                     |                |           |
| Structure             |   | 100% Studs, Girts,<br>etc. |                |           |
| Finish                | 100% Drywall                            |                            |                |           |
|                       | 100% Paint                              |                            |                |           |
| Mechanicals           |   |                            | \$124,512      |           |
| Heating               | 100% Forced Warm<br>Air                 |                            |                |           |
| Cooling               | 100% Forced Cool Air                    |                            |                |           |
| Fire Protection       |   |                            |                |           |
| Plumbing              | 9 Total Fixtures                        |                            |                |           |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

123 of 130



# Valuation Detailed Report

Policy Number: REN2218820

1/6/2023

| SUMMARY OF COSTS                              | User Provided       | System Provided      | Reconstruction   | Exclusion          |
|---|---------------------|----------------------|------------------|--------------------|
| Electrical                                    |                     | 100% Average Quality |                  |                    |
| Elevators                                     |                     |                      |                  |                    |
| Built-ins                                     |                     |                      | \$4,595          |                    |
| SUBTOTAL RC                                   |                     |                      | \$276,354        |                    |
| Depreciated Cost (48%)                        |                     |                      | \$132,650        |                    |
| ADDITIONS                                     |                     |                      |                  |                    |
| Building Items                                |                     |                      | \$13,314         |                    |
| Total Additions                               |                     |                      | \$13,314         |                    |
| <b>TOTAL RC Section1</b>                      |                     |                      | <b>\$289,669</b> |                    |
| <b>TOTAL ACV</b>                              |                     |                      | <b>\$139,041</b> |                    |
| <b>TOTAL RC BUILDING 12 Clubhouse, Flood</b>  |                     |                      | <b>\$289,669</b> |                    |
| <b>TOTAL ACV</b>                              |                     |                      | <b>\$139,041</b> |                    |
|   | Reconstruction      | Sq.Ft.               | \$/Sq.Ft.        | Depreciated        |
| LOCATION SUBTOTAL (All Buildings)             | \$12,117,444        | 78,130               | \$155            | \$5,839,176        |
| LOCATION ADDITIONS                            |                     |                      |                  |                    |
| Building Items                                | \$2,730             |                      |                  | \$2,730            |
| Custom Items                                  |                     |                      |                  |                    |
| 6' Aluminum Picket Pool Fence +/- 130 Ln Ft   | \$16,900            |                      |                  | \$16,900           |
| 6' Vinyl Privacy Pool Fence +/- 55 Ln Ft      | \$3,683             |                      |                  | \$3,683            |
| 6' Vinyl Shadow Box Pool Fencing +/- 57 Ln Ft | \$3,817             |                      |                  | \$3,817            |
| Bike Canopy +/- 70 Sq Ft                      | \$1,068             |                      |                  | \$1,068            |
| North Boat Dock +/- 2,964 Sq Ft               | \$222,300           |                      |                  | \$222,300          |
| South Boat Dock +/- 3,340 Sq Ft               | \$250,500           |                      |                  | \$250,500          |
| Swimming Pool +/- 865 Sq Ft                   | \$162,952           |                      |                  | \$162,952          |
| Swimming Pool Deck +/- 3,612 Sq Ft            | \$59,382            |                      |                  | \$59,382           |
| (2) Heat Pump, pool heaters                   | \$11,000            |                      |                  | \$11,000           |
| Location Additions Value                      | \$734,332           |                      |                  | \$734,332          |
| <b>LOCATION TOTAL, Location 1</b>             | <b>\$12,851,776</b> | <b>78,130</b>        | <b>\$164</b>     | <b>\$6,573,508</b> |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

124 of 130



# Valuation Detailed Report

## EQUIPMENT REPORT

Policy Number: REN2218820

1/6/2023

|                              | Reconstruction      | Sq.Ft.        | \$/Sq.Ft.    | Depreciated        |
|------------------------------|---------------------|---------------|--------------|--------------------|
| <b>VALUATION GRAND TOTAL</b> | <b>\$12,851,776</b> | <b>78,130</b> | <b>\$164</b> | <b>\$6,573,508</b> |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

125 of 130





# Valuation Detailed Report

## EQUIPMENT REPORT

Policy Number: REN2218820

1/6/2023

### VALUATION

|                   |                |                  |            |
|-------------------|----------------|------------------|------------|
| Valuation Number: | REN2218820     | Effective Date:  | 01/06/2023 |
| Value Basis:      | Reconstruction | Expiration Date: | 01/06/2024 |
|                   |                | Cost as of:      | 06/2022    |

### BUSINESS

The Moorings of Pinellas County Condominium  
Moorings Cove Dr  
Tarpon Springs, FL 34689 USA

### LOCATION 1 - The Moorings of Pinellas County Condominium

The Moorings of Pinellas County Condominium  
Moorings Cove Dr  
Tarpon Springs, FL 34689 USA

### Equipment: Building items and site improvements

|  | Replacement | Depreciated |
|--|-------------|-------------|
| <b>Building 1, Section1</b>                        |             |             |
| Building Items                                     |             |             |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$2,253     | \$1,149     |
| (1) Balconies, Wood frame                          | \$2,099     | \$1,070     |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$2,708     | \$1,381     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$1,294     | \$660       |
| <b>Building 2, Section1</b>                        |             |             |
| Building Items                                     |             |             |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$2,099     | \$1,007     |
| (1) Balconies, Wood frame                          | \$2,253     | \$1,082     |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$2,708     | \$1,300     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$1,294     | \$621       |
| <b>Building 3, Section1</b>                        |             |             |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

126 of 130



# Valuation Detailed Report

## EQUIPMENT REPORT

Policy Number: REN2218820

1/6/2023

| Equipment: Building items and site improvements    |             |             |
|--|-------------|-------------|
|  | Replacement | Depreciated |
| Building Items                                     |             |             |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$4,970     | \$2,386     |
| (1) Balconies, Wood frame                          | \$3,137     | \$1,506     |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$5,841     | \$2,804     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$2,868     | \$1,377     |
| <b>Building 4, Section1</b>                        |             |             |
| Building Items                                     |             |             |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$4,970     | \$2,386     |
| (1) Balconies, Wood frame                          | \$3,137     | \$1,506     |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$5,841     | \$2,804     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$2,868     | \$1,377     |
| <b>Building 5, Section1</b>                        |             |             |
| Building Items                                     |             |             |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$4,418     | \$2,121     |
| (1) Balconies, Wood frame                          | \$3,402     | \$1,633     |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$5,335     | \$2,561     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$2,538     | \$1,218     |
| <b>Building 6, Section1</b>                        |             |             |
| Building Items                                     |             |             |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$3,402     | \$1,633     |
| (1) Balconies, Wood frame                          | \$4,418     | \$2,121     |
| Canopies   |             |             |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

127 of 130



# Valuation Detailed Report

## EQUIPMENT REPORT

Policy Number: REN2218820

1/6/2023

### Equipment: Building items and site improvements

|  | Replacement | Depreciated |
|--|-------------|-------------|
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$5,335     | \$2,561     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$2,538     | \$1,218     |
| <b>Building 7, Section1</b>                        |             |             |
| Building Items                                     |             |             |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$5,037     | \$2,418     |
| (1) Balconies, Wood frame                          | \$3,534     | \$1,697     |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$5,901     | \$2,833     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$2,893     | \$1,389     |
| <b>Building 8, Section1</b>                        |             |             |
| Building Items                                     |             |             |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$3,534     | \$1,697     |
| (1) Balconies, Wood frame                          | \$5,037     | \$2,418     |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$5,901     | \$2,833     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$2,893     | \$1,389     |
| <b>Building 9, Section1</b>                        |             |             |
| Building Items                                     |             |             |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$4,771     | \$2,290     |
| (1) Balconies, Wood frame                          | \$3,976     | \$1,909     |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$5,679     | \$2,726     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$2,741     | \$1,316     |
| <b>Building 10, Section1</b>                       |             |             |
| Building Items                                     |             |             |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

128 of 130



# Valuation Detailed Report

## EQUIPMENT REPORT

Policy Number: REN2218820

1/6/2023

| Equipment: Building items and site improvements    |             |             |
|--|-------------|-------------|
|  | Replacement | Depreciated |
| Balconies  |             |             |
| (1) Balconies, Wood frame                          | \$3,976     | \$1,909     |
| (1) Balconies, Wood frame                          | \$4,771     | \$2,290     |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$5,679     | \$2,726     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$2,741     | \$1,316     |
| <b>Building 11, Section1</b>                       |             |             |
| Building Items                                     |             |             |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$8,771     | \$4,473     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$4,543     | \$2,317     |
| <b>Building 12, Section1</b>                       |             |             |
| Building Items                                     |             |             |
| Canopies   |             |             |
| (1) Wood Frame w/Pitched Roof Deck, Wall supported | \$8,771     | \$4,210     |
| Foundations  |             |             |
| (1) Foundations - Reinforced concrete, Volume      | \$4,543     | \$2,181     |
| <b>LOCATION 1 Additions</b>                        |             |             |
| Building Items                                     |             |             |
| Gazebos  |             |             |
| (1) Frame, Wood-Pitched roof, Column supported     | \$2,730     | \$2,730     |
| Custom Items                                       |             |             |
| (1) 6' Aluminum Picket Pool Fence +/- 130 Ln Ft    | \$16,900    | \$16,900    |
| (1) 6' Vinyl Privacy Pool Fence +/- 55 Ln Ft       | \$3,683     | \$3,683     |
| (1) 6' Vinyl Shadow Box Pool Fencing +/- 57 Ln Ft  | \$3,817     | \$3,817     |
| (1) Bike Canopy +/- 70 Sq Ft                       | \$1,068     | \$1,068     |
| (1) North Boat Dock +/- 2,964 Sq Ft                | \$222,300   | \$222,300   |
| (1) South Boat Dock +/- 3,340 Sq Ft                | \$250,500   | \$250,500   |
| (1) Swimming Pool +/- 865 Sq Ft                    | \$162,952   | \$162,952   |
| (1) Swimming Pool Deck +/- 3,612 Sq Ft             | \$59,382    | \$59,382    |

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

129 of 130



# Valuation Detailed Report

## EQUIPMENT REPORT

Policy Number: REN2218820

1/6/2023

| Equipment: Building items and site improvements                   |             |             |
|---|-------------|-------------|
|   | Replacement | Depreciated |
| (1) (2) Heat Pump, pool heaters                                   | \$11,000    | \$11,000    |
| LOCATION 1 - The Moorings of Pinellas County<br>Condominium TOTAL | \$911,753   | \$820,144   |
| TOTAL   | \$911,753   | \$820,144   |

To update please call us at 866-568-7853 or email us at [info@fpataadjusters.com](mailto:info@fpataadjusters.com) for pricing and more information.

CoreLogic costs include labor and material, normal profit and overhead as of date of report. Costs represent general estimates which are not to be considered a detailed quantity survey. These costs include generalities and assumptions that are common to the types of structures represented in the software.

The commercial contents values CoreLogic publishes in this report are estimates only and should not be considered the actual value of commercial contents insurance coverage that should be underwritten for the insured.

©CoreLogic. All rights reserved. CORELOGIC, the CoreLogic Logo, Commercial Express, and Commercial ExpressLync are the property of CoreLogic, Inc.

130 of 130